

To: 1 090039
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-16
API NUMBER 15- 033-20,144-1-05-01 185 R
C SE SE, SEC. 6, T 31 S, R 18 W/E
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 3372

Lease Name Burkhall OWWO Well / 1

Operator: Morrison-Dixon Oil Operations, Inc.

County Comanche 170.30

Name & Address 100 N. Main, Suite 801
Wichita, KS 67202

Well Total Depth 5240 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 473

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: 10:45 a.m. Day: 16 Month: 1 Year: 19 91

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-264-9682

were: 5 1/2" at 5238' w/150 sx cement, Perfs at 4956-61, 5126-31!, PBD 5062'

1st plug sand back to 4900' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 16 Month: 1 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4900' and dumped 5 sx cement on top of

sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

and 175 sx cement.

STATE CORPORATION COMMISSION

Pumping pressure 0 psi and shut in on vacuum.

JAN 25 1991

1-25-91 CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2700' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

FEB 13 1991

DATE

INV. NO. 30707

observe this plugging.

Signed [Signature] (TECHNICIAN)