

To: 1090301 7-12
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,087-0000
C SW NE, SEC. 9, T. 31 S, R. 18 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5134
Operator: Graham-Michaelis Corp.
Name & Address P.O. Box 247
Wichita, KS 67201

Lease Name Uhl Well # 1-9
County Comanche
Well Total Depth 5130 166.72 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 731

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1:30 p.m. Day: 12 Month: 7 Year: 19 93

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

work: 4 1/2" at 5129' w/150 sx cement, Perfs at 5000-5004, 5008-5012'
1st plug pump 1 sx hulls and 20 sx cement to 4950',
2nd plug at 1050' with 50 sx cement,
3rd plug at 760' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:45 p.m. Day: 12 Month: 7 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement over perfs to 4950',
2nd plug pulled to 1050' and spotted 50 sx cement,
3rd plug pulled to 760' and spotted 50 sx cement,
4th plug at 40' with 10 sx cement. Circulated cement.

RECEIVED
STATE CORPORATION COMMISSION

JUL 12 1993

Remarks: Used common cement by Sargent's. Recovered 3008' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)
Wichita, Kansas

INVOICED

I (did / ~~did not~~) observe this plugging.
DATE: 8-9-93

Signed [Signature]
(TECHNICIAN)

INV. NO. 38286