

To: 1 051662
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S-27

API NUMBER 15-033-20,673-0000
150' SW of
NW SE, SEC. 11, T. 31 S, R. 18 W/R
1920 feet from S section line
2115 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Lease Name Boisseau Well # 2-11

Operator: Bird Energy, Inc.

County Comanche 163.89

Name & Address P.O. Box 1612

Well Total Depth 5043 feet

Dodge City, KS 67801

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 556

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 10 a.m. Day: 27 Month: 5 Year: 19 93

Plugging proposal received from Jeff Stilletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 5043' w/125 sx cement, PBTD 4900'. Perfs at 4880-84'

1st plug pump 2 sx hulls and 40 sx common cement to 4483',

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:45 a.m. Day: 27 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 200 lbs. hulls and 50 sx cement,
displaced to 4483'.

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 250 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)
observe this plugging.

INVOICED

DATE 6-5-93

INV. NO. 37853

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1993
6-7-93
CONSERVATION DIVISION
Wichita, Kansas