

To: 1 051663 5-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,616-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 6574

Operator: Bird Energy, Inc.

Name &

Address P.O. Box 1612

Dodge City, KS 67801

C NW NE, SEC. 11, T. 31 S, R. 18 W X E

4620 feet from S section line

1980 feet from E section line

Lease Name Boisseau Well # 1-11

County Comanche 164.12

Well Total Depth 5050 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 580

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104-0187

Company to plug at: Hour: 11 a.m. Day: 27 Month: 5 Year: 19 93

Plugging proposal received from Jeff Stilletto

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4408' w/224 sx cement, PBSD 4408', Perfs at 4228-31, 4237-39'

1st plug sand back to 4175' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:05 p.m. Day: 27 Month: 5 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4175' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3000' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 6-8-93

WV. NO. 37854

Signed Richard W. Lacy
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1993
6-7-93
CONSERVATION DIVISION
Wichita, Kansas