

1 090388

1-14

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,056-0000  
C SE NW, SEC. 11, T 31 S, R 18  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name:  
Address P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Uhl "A" Well # 1  
County Comanche  
Well Total Depth 5195 168.84 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1069

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 14 Month: 1 Year: 19 94  
Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455  
wells: 4 1/2" at 5192' w/160 sx cement, PBTD 5167', Perfs at 5008-16'

- 1st plug pump 2 sx hulls and 25 sx cement over perfs with tubing,
- 2nd plug at 1100' with 50 sx cement,
- 3rd plug at 500' with 40 sx cement,
- 4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1 p.m. Day: 14 Month: 1 Year: 19 94

- ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement over perfs with tubing,
- 2nd plug at 1100' with 50 sx cement,
  - 3rd plug at 500' with 40 sx cement,
  - 4th plug at 40' with 10 sx cement through casing.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 20 1994  
1-20-94  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 4030' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)  
observe this plugging.

INVOICED

DATE JAN 21 1994  
INV. NO. 39745  
1-14

Signed \_\_\_\_\_ (TECHNICIAN)