

11-1 15-033-20103-0000

To: 1040347
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion Date 11/11/71

C NW SW, SEC. 10, T 31 S, R 18 W/E
1980 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Dillinger "A" Well # 2

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Comanche 169.16
Well Total Depth 5205 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 525

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 1 Month: 11 Year: 19 89

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5200' PBTD 5168' Perfs at 4985-95'

1st plug pump 20 sx cement at 4800',

2nd plug pump 50 sx cement at 1000',

3rd plug pump 40 sx cement at 550',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 p.m. Day: 1 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 150 lbs. hulls and 20 sx

Portland cement, stopped plug at 4868' (displaced bottom plug with drilling mud).

2nd plug shot pipe off at 2550', spotted plugs through 4 1/2" casing, pumped 50 sx cement at 1000' (pipe hung up. Shot pipe at 750'.)

3rd plug pumped 40 sx cement at 550',

4th plug pumped 10 sx cement at 40'.

Remarks: Used common cement by Sargents. Recovered 2300' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

INVOICED (11/13/89) observe this plugging.

GATE 11-13-89

INV. NO. 26377

11-1

Signed Stephen J. Pfeiffer (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION

NOV - 7 1989

11-7-89

CONSERVATION DIVISION Wichita, Kansas