

To: 1 051225  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Operator: Anadarko Petroleum Corporation  
Name &

Address P.O. Box 351

Liberal, KS 67905-0351

Abandoned Oil Well  Gas Well

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 11 a.m. Day: 26 Month: 10 Year: 19 89

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5009' PBD 5004' Perfs at 4979-84'

1st plug spot 20 sx cement at 4800',

2nd plug at 1000' with 50 sx cement,

3rd plug at 560' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5 p.m. Day: 26 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at 4800',

Spot through casing:

2nd plug at 1000' with 50 sx cement,

3rd plug at 560' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used common cement by Sargent's. Recovered 4305' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

**INVOICED**  
did not observe this plugging.

DATE 11-2-89

INV. NO. 26293

10-26

API NUMBER 15- 033-20,091-0000

C NE SW, SEC. 10, T 31 S, R 18 W/E

1980 feet from S section line

3300 feet from E section line

Lease Name Dillinger "A" Well # 1

County Comanche 162.83

Well Total Depth 5010 feet

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 539'

Input Well  SWD Well  D&A

STATE CORPORATION COMMISSION  
NOV 11 1989  
CONSERVATION DIVISION  
WICHITA, KANSAS

Signed Richard W. Lacey  
(TECHNICIAN)