

1 020358

3-11

191 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-055-20,952-0000  
NE SE NW, SEC. 8, T 23 S, R 30 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5886  
Operator: Chief Drilling, Inc.  
Name & Address: 224 E. Douglas, #530  
Wichita, KS 67202

3630 feet from S section line  
2970 feet from E section line  
Lease Name Haag Well # 3-8  
County Finney 158.92  
Well Total Depth 4890 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Chief Drilling, Inc. License Number 5886  
Address 224 E. Douglas, #530, Wichita, KS 67202

Company to plug at: Hour: 6:30 p.m. Day: 11 Month: 3 Year: 19 91

Plugging proposal received from Marion Burris  
(company name) Chief Drilling, Inc. (phone) 316-262-3791

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2045-59'

1st plug at 2060' with 50 sx cement, 2nd plug at 1050' with 80 sx cement,  
3rd plug at 525' with 30 sx cement, 4th plug at 320' with 50 sx cement,  
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,  
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 8:45 p.m. Day: 11 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2060' with 50 sx cement,

2nd plug at 1050' with 80 sx cement, 3rd plug at 525' with 30 sx cement, STATE CORPORATION COMMISSION

4th plug at 320' with 50 sx cement, MAR 15 1991

5th plug at 40' with 10 sx cement, CONSERVATION DIVISION WICHITA, KANSAS

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE APR 02 1991

INV. NO. 31263

Signed Glenn R. Barlow (TECHNICIAN)