

1041327
TO: STATE CORPORATION COMMISSION

12-04

API NUMBER 15-033-20,982-0000
140'W OF SW SW SW SEC. 12, T 31 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 470 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME BOOTH "A" WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY COMANCHE 35,000

OPERATOR LICENSE # 3959 WELL TOTAL DEPTH 682 FEET

OPERATOR: SIROKY OIL MANAGEMENT, INC PRODUCTION CSG: SIZE " FEET

NAME AND PO BOX 464 SURFACE CASING: SIZE 8 1/2" AT 25' WITH 50 SX

ADDRESS PRATT, KS 67124-0464 MIDCON CEMENT & 28 YDS. OF READY MIX TO FILL
LARGE WASH OUT AT SURFACE.

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DUKE DRILLING CO, INC LICENSE NUMBER 5929

ADDRESS 100 S MAIN, STE 410, WICHITA, KS 67202-3737

COMPANY TO PLUG AT: HOUR: 5:30 PM DAY: 03 MONTH: 12 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM JOHN ARMBRUSTER

(COMPANY NAME) DUKE DRILLING CO, INC (PHONE) 316-267-1331

WERE: LOST CIRCULATION AT 675' GL ELEVATION AT 2081. RECEIVED KANSAS CORPORATION COMMISSION

12-16-98
DEC 16 1998

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 AM DAY: 04 MONTH: 12 YEAR: 1998

ACTUAL PLUGGING REPORT WASHED HOLE BACK DOWN TO 300' W/OPEN ENDED DRILL PIPE. SPOT 50 SX OF MIDCON CEMENT AT 300' THRU DRILL PIPE. TRIP DRILL PIPE OUT. LET CEMENT SET. TRIP BACK IN W/DRILL PIPE. HOLE DIDN'T STAY OPEN. FOUND CEMENT (UNSET) STRUNG THROUGHOUT HOLE. TRIP OUT OF HOLE W/DRILL PIPE. PUT ON BIT & WASHED HOLE BACK DOWN TO 300'. TRIP OUT W/BIT. RUN DRILL PIPE BACK IN OPEN ENDED. SPOTTED 50 SX OF COMMON CEMENT W/3% CC. TRIP OUT W/DRILL PIPE LET CEMENT SET. WAIT ON MORE CEMENT. TRIP IN HOLE W/DRILL PIPE & TAG TOP OF CEMENT AT 240'. CIRCULATED CEMENT FROM 240' TO SURFACE W/200 SX OF 60/40 POZMIX 2% GEL 3%CC. CIRCULATED RATHOLE WITH 15 SX CEMENT.

REMARKS: CEMENT WORK DONE BY HALLIBURTON (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I DID OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

DEC 17 1998 60469

12-04

AUG 27 1998