

1 050277

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 033-20,650-0000

C SW NW, SEC. 13, T 31 S, R 18 WXR

1980 feet from N/X section line

1980 feet from W/R section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5673

Lease Name Pyle Well # 1

Operator: W. L. Kirkman, Inc.

County Comanche

Name & Address P. O. Box 18611

Well Total Depth 4900 154.25 feet

Wichita, KS 67218

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 553

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address P. O. Box 18611, Wichita, KS 67218

Company to plug at: Hour: 3:30 pm Day: 3 Month: July Year: 19 84

Plugging proposal received from Larry Harris

(company name) Aldebaran (phone) 316-672-7471

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1100' with 50 sx cement

2nd plug at 600' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement.

Plug water well with 5 sx cement Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 3 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1100' with 50 sx cement, 2nd plug at 600' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement, plug water well with 5 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Boui

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

DATE 7-13-84

INV. NO. 2471

7-3

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

JUL 06 1984
7-6-84
CONSERVATION DIVISION
Wichita, Kansas