

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22217-00-01
Spot: NENW Sec/Twnshp/Rge: 8-30S-13W
4620 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: DON LAMBERT 1-B Well Number: OWWO
County: BARBER Total Vertical Depth: 4730 feet

Operator License No.: 5506 Conductor Pipe: Size 13.375 feet: 135 8153.73
Op Name: WOOLSEY PETROLEUM CORPORATION Surface Casing: Size 8.625 feet: 1064 WITH 450 SX CMT
Address: 125 N. MARKET, SUITE 1000 Production: Size 5.5 feet: 4734 WITH 125 SX CMT
WICHITA, KS 67202 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/12/2002 8:15 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: SHAWN TILLISTON Company: WOOLSEY PETROLEUM Phone: (316) 267-4379

Proposed Plugging Method: Sand back to 4580', spot 5 sx cmt w/bailer, cut casing and plug sa follows thorough 5 1/2" casing: @1100' pump 15 sx gell and 50 sax cement, at 400' 40 sx ce,emt& @ 40' cememt to surface with 10 sx using 60/40 POZ and 6% Gel.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/12/2002 9:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4694'. PERFS AT 4674-84'. CIBP @ 4668'. PERFS AT 4630-50'. DUG OUT AND CHECKED CMT TOP ON 13 3/8" X 8 5/8" ANNULUS. CMT TOP 1' FROM SURFACE. SANDED BACK TO 4578' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LAID DOWN CASING & RUN TUBING IN TO SPOT PLUGS. 1ST PLUG AT 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 20 2002
3-20-02
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3300' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE Mar 20-02
INV. NO 2002061552

MAR 14 2002

FORM 68-2/3