

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22176-00-00
Spot: W2NESE Sec/Twnshp/Rge: 8-30S-13W
1980 feet from S Section Line, 780 feet from E Section Line
Lease/Unit Name: LEMON JOHN Well Number: 3-A
County: BARBER Total Vertical Depth: 4750 feet

Operator License No.: 3536
Op Name: RAMCO ENERGY CORPORATION
Address: 2699 STIRLING ROAD, SUITE C102
FT. LAUDERDALE, FL 33312

Conductor Pipe: Size 13.375 feet: 105 8154.38
Surface Casing: Size 8.625 feet: 1055 WITH 300 SX CMT
Production: Size 5.5 feet: 4742 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/05/2002 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND TO 4470' & 5 SX CMT. 1ST PLUG AT 1080' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 07/05/2002 3:30 PM

Witness Type: Plugging Operations Were Not Witnessed
KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4742'. PERFS AT 4562-88'. SAND BACK TO 4470' & 5 SX CMT ON TOP WITH BAILER. 13 3/8" X 8 5/8" ANNULUS HAS CMT DOWN 4". 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 1000'. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

RECEIVED
JUL 19 2002
7-19-02
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 3902' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey
(TECHNICIAN)

INVOICED JUL 16 2002

DATE 7-19-02
INV. NO. 2003060066 MP

Form 2/03