

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-033-20627-00-00

LEASE NAME Davis

WELL NUMBER 1-33

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 33 TWP. 32 SRGE. 16 (E) or (W)

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Evergreen Operating Corp.

ADDRESS 1512 Larimer St., Ste. 1000, Denver CO 80202 COUNTY Commanche

PHONE# (303) 534-0400 OPERATORS LICENSE NO. 4526

Date Well Completed 6/22/92

Character of Well Gas

Plugging Commenced 3/27/92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/01/92

The plugging proposal was approved on 2/26/92 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 4973' Bottom 5087' T.D. 5087'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0'	502'	8-5/8"	501'	0'
		0'	5080'	4-1/2"	5080'	3199'
		0'	4980'	2-3/8"	4980'	4980'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Set CIBP @ 4900' w/35' cement on top. shot off 4 1/2" casing @ 3206', pumped 30 sx cement @ 3206'. Pumped 50 sx cement from 552' to 431'. Capped surface casing w/ 10 sx cement from 33' to 3'. All intervals were filled w/9.5 ppg mud. Cut off surface csg @ 3', welded on appropriate ID plate.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Reeves Casing, Inc. License No. 03003

Address P.O. Box 94804, Oklahoma City, OK 73143


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Evergreen Operating Corp.

STATE OF Colorado COUNTY OF Archuleta, ss.

Stephanie J. Basey (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Stephanie Basey

1512 Larimer St., Ste. 1000  
 (Address) Denver, CO 80202



SWORN TO before me this 24th day of April

Sandra L. Seibert  
 Notary Public

Expires: 4/1/95

