

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Dorby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-033-20-608-0000

LEASE NAME Unruh

WELL NUMBER 4-4

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div. C  
office within 30 days.

SW NE Ft. from S Section Line

\_\_\_\_\_ Ft. from E Section Line

SEC. 4 TWP. 31S RGE. 8W (E) or (W)

COUNTY Comanche

LEASE OPERATOR Graham - Michaelis Corporation

ADDRESS Box 232 Russell, Kansas 67665

PHONE 913 483-3136 OPERATORS LICENSE NO. 5134

Date Well Completed \_\_\_\_\_

Character of Well Oil

Plugging Commenced 12-12-96

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-13-96

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 5085

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	618	0
				4 1/2	5084	4026

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pump 20 sks. of cement & 3 sks. of hulls to 4700  
Pump 50 sks. of cement from 1,000' to 900'  
Pump 50 sks. of cement from 630' to 530'  
Put 10 sks. of cement from 40' to 0' Cut off & cap 8 5/8 4' below ground level  
(If additional description is necessary, use BACK of this form.) Weld I.D. plate

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547


Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack King

(Address) P.O. Box 247, Wichita, KS 67201



AND SWORN TO before me this 31 day of January, 19 97

Glenda G. Newell  
Glenda G. Newell Notary Public

My Commission Expires: 7/2/97