


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec 8 Twp. 32S Rge. (E) 16 (W)

Location as "NE/CNW/SW" or footage from lines C NW/4 SE/4
Lease Owner Graves Drilling Co. - Beacon Resources Corp.
Lease Name Perry Well No. 1
Office Address 505 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 24 1969
Application for plugging filed " 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation Depth to top Bottom Total Depth of Well 4970 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|---------|--------|------------|
| | | | | 10 3/4" | 261' | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 250 ft., set plug, 35 sacks cement
Mud to 40 ft., set plug, 15 sacks cement, to surface

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1969
CONSERVATION DIVISION
Wichita, Kansas
10-28-69


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
John C. Graves (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
505 Union Center, Wichita, Kansas (Address)

Subscribed and sworn to before me this 27th day of October, 1969
July 28, 1970
Mary Ann Scott Notary Public



ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling - Beacon Resources DRILLING COMMENCED: 10/11/69
Union Center, Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 10/24/69
505 Union Center,
Wichita, Kansas 67202

CASING RECORD: Set 10 3/4" surface casing @ 261', with 225 sacks of cement.
LOCATION: #1 Perry
C NW/4 SE/4 Sec. 8-32S-16W
Comanche County, Kansas

| | | | |
|------|---|------|-----------------|
| 0 | - | 80 | Red bed & clay |
| 80 | - | 800 | Red bed |
| 800 | - | 1232 | Shale & red bed |
| 1232 | - | 1421 | Shale |
| 1421 | - | 4102 | Lime & shale |
| 4102 | - | 4115 | Shale |
| 4115 | - | 4163 | Shale & lime |
| 4163 | - | 4215 | Shale & sand |
| 4215 | - | 4247 | Shale |
| 4247 | - | 4313 | Lime & shale |
| 4313 | - | 4735 | Lime |
| 4735 | - | 4829 | Lime & shale |
| 4829 | - | 4970 | Lime |
| 4970 | | | T.D. |

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1969
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct,
to the best of my knowledge.

GRAVES DRILLING COMPANY, INC.

John C. Graves
John C. Graves, President

STATE OF KANSAS
SEDGWICK COUNTY

Subscribed and sworn to before me, a Notary Public, this 27th day of
October, 1969.

My Commission Expires: July 28, 1970

Mary Ann Scott
Mary Ann Scott, Notary Public

