

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Comanche County, Sec. 9 Twp. 32 Rge. (E) 16 (W)

NORTH


Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines SW SW NE  
 Lease Owner Rupp-Ferguson Oil Co.  
 Lease Name Schuette Well No. 1  
 Office Address 523 Petroleum Bldg., Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
 Date well completed 6-27-56 19  
 Application for plugging filed 6-27-56 19  
 Application for plugging approved 6-27-56 19  
 Plugging commenced 6-27-56 19  
 Plugging completed 6-27-56 19  
 Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5449 Feet  
 Show depth, and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8"	350	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole w/heavy mud to 345, plug, 1/2 sack hulls, 35 sacks cement through drill pipe. Fill w/mud to 30', 1/2 sack hulls, plug, 1/2 sack hulls, fill with cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.  
 Address 523 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox  
523 Petroleum Bldg., Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1956

My commission expires June 4, 1959

Helen Horine  
 Notary Public.

PLUGGING  
 FILE SEC. 9 T. 32 R. 16W  
 BOOK PAGE 76 LINE 22

7-3-56  
 DIVISION

CONTRACTOR'S WELL LOG

No. 1 Schuette  
SW SW NE, Sec. 8-32-16W,  
Cossanche County, Kansas

D & A  
Elev. 1926 FT

Commenced: 6-4-56

Completed: 6-27-56

Contractor: Rupp-Ferguson Oil Co.

Set 250' of 13 3/8" surface casing with 250 sacks cement

Figures Indicate Bottom of Formation


130 red bed  
205 Anhydrite  
248 red bed  
260 Anhydrite  
1200 shale & shells  
1385 salt  
1600 shale & shells  
2050 lime & shale  
2525 lime  
3535 lime & shale  
3635 lime  
4100 lime & shale  
4220 sand, lime, shale  
4332 KC  
4707 lime  
4787 lime & shale  
5012 Miss.  
5150 shale & lime  
5227 lime, chert & shale  
5255 cherty lime & shale  
5375 cherty lime  
5320 lime & shale  
5401 Simpson  
5449 Arb. SD

STATE OF KANSAS) SS:  
LEDGWICK COUNTY)

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Schuette well.

  
L. W. KNOX

Subscribed and sworn to before me this 2nd day of July, 1956.

  
Helen Horine  
Notary Public

My Commission Expires June 4, 1959.

PLUGGING			
FILE	SEC	T. <sup>32</sup> <del>26</del>	R. 16W
BOOK	PAGE	LINE	