


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Locate well correctly on above
Section Plot

Comanche County, Sec. 10 Twp. 32 Rge. 16W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE/4

Lease Owner Patton Oil Company
Lease Name Schuette A#1 Well No. _____
Office Address Hoisington, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____

Date Well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 11/21/76 19____
Plugging completed 12/ 2/76 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4736
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	348	none
				5 1/2"	4732	3160'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4700' and set 5 sacks cement. Loaded hole with 90 bbls. water, shot pipe at 2972', 3893', 3804', 3724', 3636', 3556', 3514', 3347', 3277', pulled 76 joints. Set rock bridge at 240' and ran 25 sacks cement, rock bridge 40' to 30' and ran 10 sacks cement.

PLUGGING COMPLETE.

DEC 14 1976
12-14-76
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor VOTH CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
WALTER VOTH (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

Walter Voth

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1976

My commission expires



Margaret Melcher
Notary Public.

Drillers Log

No. *A1* Schuette

CASING RECORD:	COMPANY:	Patton Oil Company	DESCRIPTION:
13 3/8" @40'	CONTRACTOR:	Red Tiger Drilling Company	C/NE $\frac{1}{4}$
w/100 sx cmt	COMMENCED:	August 6, 1976	Sec.10-T32S-R16W
8 5/8" @348'	COMPLETED:	August 16, 1976	Comanche County,
w/280 sx cmt			Kansas
5 $\frac{1}{2}$ " @ 4735.5'			
w/125 sx cmt			
TOTAL DEPTH: 4736'			ELEVATION: 1805' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	40	
Redbeds	40	333	
Redbeds & Shale	333	1153	
Redbeds & Shale	1153	1310	
Shale	1310	1730	
Shale & Lime	1730	1935	
Shale & Lime	1935	2110	
Shale & Lime	2110	2250	
Lime & Shale	2250	2405	
Lime	2405	2560	
Lime & Shale	2560	2596	
Lime & Shale	2596	2645	
Lime & Shale	2645	2825	
Lime & Shale	2825	2990	
Lime & Shale	2990	3155	
Shale & Lime	3155	3300	
Shale & Lime	3300	3420	
Lime & Shale	3420	3580	
Lime	3580	3785	
Lime	3785	3930	
Lime	3930	4090	
Lime & Shale	4090	4240	
Lime & Shale	4240	4400	
Lime & Shale	4400	4520	
Lime	4520	4630	
Lime	4630	4680	
Lime	4680	4705	
Lime	4705	4736	
RTD		4736	


RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1976


CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY


Jean Stocks

Subscribed & sworn to before me this 20th day of August, 1976.




Notary Public