

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,831-00-01

LEASE NAME Wilson

WELL NUMBER 1-2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Ft. from S Section Line

660 Ft. from E Section Line

LEASE OPERATOR Raydon Exploration, Inc.

SEC. 2 TWP. 32 SRGE. 18 ~~18~~ (W)

ADDRESS 9400 N. Broadway - Suite 400
Oklahoma City, OK 73114

COUNTY Comanche

PHONE#(316) 624-0156 OPERATORS LICENSE NO. 30604

Date Well Completed 8-20-91

Character of Well D & A

Plugging Commenced 8-20-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-20-91

The plugging proposal was approved on August 20, 1991 (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, Is well log attached? No

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 6050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	629'	None AUG 27 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
Spotted 40 sx. cement at 6050' thru drill pipe.
Spotted 50 sx. cement at 1070' thru drill pipe.
Spotted 50 sx. cement at 700' thru drill pipe.
Spotted 10 sx. cement at 40' thru drill pipe. Spotted 15 sx. cement in rathol.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor White & Ellis Drilling, Inc. License No. 5420

Address P. O. Box 48848, Wichita, KS 67201-8848

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raydon Exploration, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Michael L. Considine (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Michael L. Considine


(Address) P. O. Box 48848
Wichita, KS 67201-8848

SUBSCRIBED AND SWORN TO before me this 23rd day of August, 19 91

My Commission Expires _____

Carolyn J. Tjaden
CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. Sept. 5, 1992

Notary Public



15-033-20831-20-00

WHITE

AND ELLIS DRILLING, Inc.

DRILLERS LOG

OPERATOR: Raydon Exploration, Inc., 9400 N. Broadway - Suite 400
 Oklahoma City, OK 73114
 CONTRACTOR: White & Ellis Drilling, Inc., P. O. Box 48848,
 Wichita, Kansas 67201-8848

Lease Name Wilson Well No. 1-2

Sec. 2 T. 32S R. 18W Spot N/2 NE SE

County Comanche State Kansas Elev. _____

Casing Record:

Surface: 8 5/8" @ 629' with 290 sx.

Production: _____ @ _____ with _____ sx.

Type Well: D & A Total Depth 6050'

Drilling Commenced 8-6-91 Drilling Completed 8-20-91

Formation	From	To	Tops	
Cellar	0	5	Heebner	4283
Sand & Clay	5	355	Kansas City	4438
Rock	355	368	Miss	5075
Red Bed & Clay	368	566	Miss-Warsaw	5190
Shale	566	1218	Osage	5327
Shale & Shells	1218	1628	Miss	5437
Lime & Shale	1628	2479	Kinderhook	5608
Shale & Lime	2479	2690	Viola	5661
Lime & Shale	2690	4925	Viola/Simpson	5880
Lime	4925	6050	Simpson/ Arbuckle	5983

RECEIVED
 COMMISSION

AUG 27 1991

CONSERVATION DIVISION
 Wichita, Kansas