


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-033-00036-00-00 (sent to state)
R
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec. 22 Twp. 32s Rge. 16W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW NE
Lease Owner Kern Drilling Company
Lease Name Schulte Well No. # 1
Office Address Box 107 Liberal, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed yes 19
Application for plugging approved yes 19
Plugging commenced 7-3-60 19
Plugging completed 7-10-60 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lac Kamp
Producing formation Depth to top Bottom Total Depth of Well 4848 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,835'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 7-3-60. Plugging completed 7-10-60. Measured into total depth, 4848'. Plugged off bottom: (After killing gas in well.) Dumped 10 sacks of cement at 4848'. Worked and shot casing. Shot 5 1/2" casing at 2835'. Pulled and laid down casing after building rack and slide. Set 10' rock bridge at 308'. Dumped 20 sacks of cement on rock bridge. Mudded hole up to 40'. Set a 10' rock bridge at 40'. Capped the well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1960

My commission expires December 8th, 1963.

Kayann Jenkins Notary Public.



also m. guide

RECEIVED
STATE CORPORATION COMMISSION

6150

APR 26 1966

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY: KERN DRILLING CO., INC.
CONTRACTOR: KERN DRILLING CO., INC.
LEASE: SCHUETTE #1
LOCATION: C-SW-NE-Sec. 2-32-16W
Comanche County, Kansas
COMMENCED: 3-26-60
COMPLETED: 4-23-60
CASING: Set 298' surface casing
8-5/8 set @ 308' cemented
w/175 sks. pozmix 2% cal.
chloride - Set 5400' of
4-1/2 casing

0- 311	Rock & Red rock
311-1396	Shale & Sand
1396-1751	Red shale-lime-anhydrite
1751-2204	Red shale-sand
2204-2366	Red shale, chalky lime
2366-2731	Red shale-sand-chalky lime
2731-2954	" " " Lime
2954-3504	Red Shale-sand-lime
3504-4277	Chalky Lime-Shale
Last returns @ 4220	
4277-4784	Shale, sand, Lime
4784-4788	Core #1
4788-4812	Core #2
4812-4834	Shale-sand-Lime
4834-4973	Chert-Lime-Shale
4973-5091	Chert-Lime-Shale
5091-5315	Shale-sand-chert-lime
5315-5400	Sand stone-chert-shale
5400	T. D.