

15-033-20151-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Comanche County, Sec. 5 Twp. 32S Rge. (E) 18 (W)

Location as "NE/CNWxSWx" or footage from lines. C NE SW SW

Lease Owner Graham-Michaelis Corporation

Lease Name Herd Well No. 1-5

Office Address P. O. Box 247, Wichita, Kansas 67201

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed September 15, 1974

Application for plugging filed September 13, 1974

Application for plugging approved September 16, 1974

Plugging commenced September 15, 1974

Plugging completed September 15, 1974

Reason for abandonment of well or producing formation

Non-commercial

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was com-

menced? Yes (verbal)

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein

Producing formation none Depth to top Bottom Total Depth of Well 5262 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	613'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 35 sacks cement at 300' (50/50 posmix)

15 sacks cement at 40' (50/50 posmix)

2 sacks cement in rat hole.

By Sun Cementing Company

10-02-1974
RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick ss.

Jack L. Yinger (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Yinger

P. O. Box 247, Wichita, Kansas 67201

(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of October, 1974

My commission expires

MURIEL F. C. JERAM
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMMISSION EXPIRES
JULY 25, 1976

Muriel F. C. Jeram
Notary Public.

15-033-20151-00-00

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

Herd #1-5 5
Ne SW-SW Sec-32S-18W
Comanche County Kansas

Commenced: 8-28-74

Completed: 9-15-74

OPERATOR: GRAHAM-MICHAELIS CORP.

From	Depth To	Formation	Remarks
0	215	Sand	
215	240	Shale	
240	1277	Redbed	
1277	1960	Shale-Shells	
1960	2519	Shale-Lime-Shells	
2519	2610	Shale-Lime	
2610	2841	Broken Lime	
2841	3855	Lime-Shale	
3855	3985	Shale-Lime	
3985	4279	Lime	
4279	4615	Lime-Shale	
4615	5240	Lime	
5240	5260	Lime-Shale	
	5260 TD		

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1974
CONSERVATION DIVISION
Wichita, Kansas

10-02-1974

DRY & ABANDONED

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled NE-SW-SW Sec 5-32S-18W Comanche County Kansas to the best of my knowledge and belief.

James S. Sutton II
JAMES S. SUTTON II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 24th day of September, 1974, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Marjorie Hall
MARJORIE HALL-NOTARY PUBLIC



MY Commission Expires: November 29th, 1975