


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

COMANCHE County. Sec. 31 Twp. 31s Rge. 18 (E) (W)  
Location as "NE/CNWxSWx" or footage from lines NW NW SE  
Lease Owner PETROLEUM, INC.  
Lease Name YOST Well No. 1  
Office Address R.R. #2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed NOVEMBER 11 19 67  
Application for plugging filed NOVEMBER 16 19 67  
Application for plugging approved NOVEMBER 16 19 67  
Plugging commenced NOVEMBER 11 19 67  
Plugging completed NOVEMBER 11 19 67  
Reason for abandonment of well or producing formation NO PRODUCIBLE FORMATION

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 5394 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FRDM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8"	419'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUD TO 300', 1/2 SACK HULLS, WOODEN PLUG, PLACED 20 SACKS CEMENT ON TOP OF PLUG. MUD TO 40', 1/2 SACK HULLS, WOODEN PLUG, PLACED 8 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

STATE CORPORATION COMMISSION  
NOV 26 1967  
11-26-67  
CONS. DIVISION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
MONTE CHADD (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*

R.R. #2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 16 day of NOVEMBER, 19 67

My commission expires MAY 28, 1969

*Richard W. D. Quinlan*  
Notary Public.

15-033-20018-0000

# WELL LOG

COMPANY Petroleum, Inc.

SEC. 31 T. 31S R. 18W

FARM Yost

NO. 1

LOC. NW NW SE


TOTAL DEPTH 5394'

COUNTY Comanche

COMM. 10-23-67

COMP. 11-11-67

CONTRACTOR Garvey Drilling Company



CASING

8 5/8" @ 419' w/325 sx

ELEVATION 2144' K.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 80' Sand and Red Bed
- 245' Sand
- 377' Red Bed and Shale
- 420' Anhydrite
- 1058' Shale and Shells
- 1345' Shale, Anhydrite and Lime
- 1750' Shale and Shells
- 2328' Lime, Shells and Shale
- 2485' Lime and Shale
- 2885' Lime
- 3670' Lime and Shale
- 3770' Lime
- 3966' Lime and Shale
- 3990' Shale
- 4567' Lime and Shale
- 4680' Lime
- 4710' Lime and Shale
- 5230' Lime
- 5287' Chalk, Lime and Shale
- 5394' Lime
- 5394' RTD

**RECEIVED**  
 STATE CORPORATE COMMISSION  
 NOV 26 1967  
 11-26-67  
 CONSERVATION DIVISION  
 Wichita, Kansas

State of Kansas }  
 County of Barton } SS

I, James R. Rodgers of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Yost No. 1 well.

James R. Rodgers

Subscribed and sworn to before me this 15th day of November 19 67

My Commission Expires: November 5th, 1969

Richard S. Doop  
 NOTARY PUBLIC