

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Comanche County. Sec. 32 Twp. 31 Rgs. (E) 18(W)

Location as "NE/CNW/SW" or footage from lines NW NW NW  
Lease Owner Rupp-Ferguson Oil Co.  
Lease Name Brinkman Well No. 1  
Office Address 523 Petroleum Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 11-7-54 19  
Application for plugging filed 11-7-54 19  
Application for plugging approved 11-7-54 19  
Plugging commenced 11-7-54 19  
Plugging completed 11-7-54 19  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren H. Horner  
Producing formation Depth to top Bottom Total Depth of Well 5261 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				20"	145'	0
				13 3/8"	437'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 35'. Built bridge with plug & hulls. Cemented with 15 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
DIVISION  
11-18-54  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.  
Address 523 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. W. Knox  
523 Petroleum Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of November, 19 54

Helen Horine  
Notary Public.

My commission expires 6-4-55

PLUGGING  
FILE SEC. 32 T. 31 R. 18W  
BOOK PAGE 26 LINE 2

CONTRACTOR'S WELL LOG

COMPANY	Rupp-Ferguson Oil Co.
CONTRACTOR	Rupp-Ferguson Oil Co.
FARM	Brinkman #1
LOCATION	NW NW NW Sec. 32-31S-10W Comanche County, Kansas
COMMENCED	October 13, 1954
COMPLETED	November 7, 1954

0	100	Sand
100	115	Sandy shale
115	145	Sand & shale
145	270	Sand
270	295	Sand & clay
295	350	Red bed
350	380	Sand
380	430	Red bed
430	456	Anhydrite
456	720	Red bed
720	980	Shale, shells & red bed
980	1350	Salt
1350	1472	Shale & shells
1472	1600	Shale & salt
1600	1880	Shale & shells
1880	2150	Shale & sand
2150	2315	Lime & shale
2315	2375	Lime
2375	2925	Lime & shale
2925	2980	Lime, sand & shale
2980	3795	Lime & shale
3795	3992	Lime
3992	4157	Shale & lime
4157	4211	Lime, shale & sand
4211	4221	Sand
4221	4354	Sand, shale & lime streaks
4354	4625	Lime & shale
4625	4835	Lime
4835	5115	Lime & shale
5115	5261	Lime
	5261	Rotary Total Depth

Set 20" surface casing at 145' with 250 sacks cement.  
 Set 13" surface casing at 437' with 625 sacks cement.

11-18-54

Dry and Abandoned

STATE OF KANSAS )  
 ) ss  
 COUNTY OF SEDGWICK )

I, L. W. KNOX, Landman for Rupp-Ferguson Oil Co., do hereby certify that the above and foregoing is a true and correct copy of the log of the BRINKMAN #1, NW NW NW of Section 32-31S-10W, Comanche County, Kansas as reflected by our files.

*L. W. Knox*  
 L. W. Knox

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 11th day of November, 1954.

*Katherine E. Allan*  
 Notary Public

My commission expires  
 January 16, 1957

PLUGGING  
 FILE DEC 32 131 18 1/2  
 BOOK PAGE 76 LINE 2