


15-033-19006-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec. 35 Twp. 31S Rge. 18 (E) 18 (W)
Location as "NE/CNW/SW" or footage from lines 2105 N & 1896 W of SE Corner
Lease Owner United Producing Co., Inc.
Lease Name Wm. McCrary Well No. 1-B
Office Address P.O. Box 1913, Charleston 27, W. Virginia.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed June 27 19 53
Application for plugging filed July 8 19 53
Application for plugging approved July 9 19 53
Plugging commenced July 15 19 53
Plugging completed July 30, 19 53
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation Mississippian Depth to top 5116 Bottom 5573 Total Depth of Well 6051 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, clay, shale and sand	Fresh Water	Surface	288	20" O.D.	230'	None
Sand, Red Bed	" "	288	517	13 3/8"	500'	"
Red Bed, Lime, Shale, Anhydrite	Salt Water	517	2510	8 5/8"	2494'	556'
Lime, Shale, Chert	Shows-Slight oil & saltwater	2510	6051	5 1/2" OD	5267'	3266'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped cement into 5 1/2" OD casing to cement off perforations at 5134- 5154 - Halliburton wood plug broke and cement stopped at 3450 - 5 1/2" OD casing came loose at 3246 - Pumped in drilling mud, 3450 to 2475 - wood bridge at 2475. Rock and cement 2475 to 2400, dumped mud from 2400 to 450 - wood bridge at 450 - rock and cement 450- to 400 - dumped heavy mud from 400 to 300 - dumped rock and cement from 30 to 4 (bottom of cellar).

Correspondence regarding this well should be addressed to: A. H. Robinson, Dist. Supt., United Producing Co., Inc., P.O. Box 127, Satanta, Kansas

STATE CORPORATION COMMISSION
AUG - 8 1953
8-8-53
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. R. Barnes, Russell, Kansas
Address _____

STATE OF Kansas, COUNTY OF Haskell, ss.
Arthur H. Robinson (employee of owner) or owner or operator of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arthur H. Robinson

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of August, 19 53

William B. Claunch
Notary Public.

My commission expires August 30, 1956

24-7868-5 3-53-20M

Orig. & One; Corporation Commission
cc: C. L. Staats
C.B. Wilson, Jr.
file

PLUGGING
FILE SEC 35 T 31 R 18 W
BOOK PAGE 113 LINE 24

15-033-19006-0000
 UNITED PRODUCING COMPANY, INC
 McCreary No. 1 Well
 NW SE Section 35-31S-18W

Commenced: May 18, 1953
 Completed: June 20, 1953

CASING RECORD

Set 20" Casing @ 230' w/700 Sx.
 Set 13 3/8" Casing @ 517' w/600Sx.
 Set 8-5/8" Casing @ 2506' w/400 Sx.
 Set 5 1/2" Casing @ 5242' w/250 Sx.

Sand & Surface Clay	0	85	Lime & Shale	6002	6051
Sand, Clay & Shells	85	150			
Sand & Shale	150	161	Total Depth	6051	
Sand	161	260			
Sand & Shale	260	290			
Sand, Gravel & Red Bed	290	330			
Sand & Red Bed	330	517			
Red Bed & Shells	517	611			
Red Bed, Shale & Shells	611	761			
Red Bed, Shale, Shells, & Anhy.	761	954			
Shale & Anhydrite	954	1003			
Anhydrite	1003	1132			
Shale & Anhydrite	1132	1428			
Red Bed & Anhydrite	1428	1650			
Shale, Anhy., Lime & Salt	1650	1700			
Shale, Anhy., Shells & Salt	1700	1770			
Shale, Anhydrite & Salt	1770	1985			
Shale & Anhydrite	1985	2305			
Anhydrite, Shale & Salt	2305	2337			
Anhydrite, Shale & Lime	2337	2398			
Shale & Lime	2398	2510			
Lime	2510	2570			
Lime & Sand	2570	2700			
Sandy Lime & Shale	2700	2735			
Sandy Shale & Lime	2735	2953			
Lime & Shale	2953	4358			
Lime	4358	4533			
Lime, Cherty	4533	4547			
Lime & Shale	4547	4624			
Lime & Shale, Cherty	4624	4660			
Lime, Cherty	4660	4678			
Lime	4678	4937			
Lime, Cherty	4937	4975			
Lime	4975	4977			
Lime, Cherty	4977	5037			
Lime	5037	5248			
Lime, Cherty & Shale	5248	5294			
Lime	5294	5380			
Lime, Cherty & Shale	5380	5423			
Lime & Chert	5423	5515			
Lime, Cherty	5515	5536			
Lime	5536	5609			
Lime & Chert	5609	5710			
Lime	5710	5791			
Lime & Chert	5791	5806			
Lime & Shale	5806	5847			
Lime, Cherty	5847	5864			
Lime	5864	5866			
Lime & Sand	5866	5897			
Lime & Shale	5897	5970			
Shale, Sand & Lime	5970	6002			

PLUGGING
 FILE SEC. 337-31R-18W
 BOOK PAGE 113 LINE 24

RECEIVED
 STATE CORPORATION COMMISSION

JUL 9 1953
 7-9-53
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF OKLAHOMA)
) ss
 County of Tulsa)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the McCrary #1 Well located in the NW/4 of the SE/4 of Section 35, T31S, R18W, Commanche County, Kansas.

HELMERICH & PAYNE, INC.
 (s) H. H. Griffin
 Vice President

Subscribed and sworn to before me a Notary Public this 30th day of June, 1953

(s) Douglas B. Wright
 Notary Public

My Commission Expires March 13, 1954