


15-033-00063-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Comanche County, Sec. 35 Twp. 31S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines 1980 North & 1980 West of SE Corner
Lease Owner United Producing Co., Inc.
Lease Name Wm McGrary Well No. 1-A
Office Address P.O. Box 1913, Charleston 27, West Virginia
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 17 1953
Application for plugging filed May 26 1953
Application for plugging approved See Previous Correspondence 19
Plugging commenced October 8 1953
Plugging completed October 10 1953
Reason for abandonment of well or producing formation Cave In Water Sand

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives, Pratt, Kansas
Producing formation Domestic Water Sand Depth to top 93 Bottom 373 Total Depth of Well 403 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Soil & Clay	Dry	0	93	None		
Fine Water Sand	Fresh Water	93	176	11		
Coarse Water Sand	" "	176	373			
Blue Shale & Red Bed	Dry	373	403			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from None feet to None feet for each plug set.

Fine sand washed out, Hole caved leaving crater at ground surface. Lost 90 feet of drill collars, bit, 311 feet of drill pipe and blow out preventer in crater. Skidded rig to Well #1-B to drill new hole. Crater was kept filled with water until all settling discontinued. Drill pipe was cut off below farming depth and the crater filled back to natural ground level with a bull dozer.

Correspondence regarding this well should be addressed to

A.H. Robinson, Dist. Supt., United Producing Co., Inc.,

P.O. Box 127, Satanta, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E.T. Young, Dirt Contractor, And By Company Labor
Address Ulysses, Kansas

STATE OF KANSAS, COUNTY OF HAS KELL, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William B. Claunch*

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1953

William B. Claunch
Notary Public.

STATE CORPORATION COMMISSION

My commission expires Aug. 30 1956

24-7368-S 3-53-20M

PLUGGING
FILE SEC 35 T 31 R 18W
BOOK PAGE 103 LINE 43

OCT 16 1953
10-16-53
CONSERVATION DIVISION
Wichita, Kansas

Wm. McCrary #1

Equipment Lost By Helmerich & Payne, Inc., In The Original Hole

- 1 Each 12 $\frac{1}{2}$ " Rotary Rock Bit
- 3 Each 8" Drill Collars
- 2 Each 6" Drill Collars
- 7 Joints 4 $\frac{1}{2}$ " Drill Pipe
- 1 Each Shaffer Double Blow-Out Preventer

Approximate Log Of Original Hole

	Surface	to	185 ¹⁵⁰	Soil and Clay
150	185	to	320	Fine to Course Water Sand
	320	to	350	Red Bed
	350	to	403	Very Coarse Water Gravel

PLUGGING
 FILE SEC 357-31R-184
 BOOK PAGE 103 LINE 43

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 27 1953
 5-27-53
 CONSERVATION DIVISION
 Wichita, Kansas