

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Gomanche County. Sec. 14 Twp. 31 Rge. 18 (E) W (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines G NW NW

Lease Owner W. J. Coppinger

Lease Name 5 Schrock Well No. 1

Office Address 507 Union National Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 6 19 58

Application for plugging filed October 6 19 58

Application for plugging approved October 6 19 58

Plugging commenced October 6 19 58


Plugging completed October 6 19 58

Reason for abandonment of well or producing formation no oil in commercial quantities found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rivas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5232 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	382'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with extra heavy rotary mud from total depth (5232') to 350'. Set Halliburton Plug at 350' with 20 sacks cement. Filled hole with extra heavy rotary mud from Plug #1 to 40'. Set Halliburton Plug at 40' cemented with 10 sacks cement on top.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Capitt Drilling, Inc.

Address 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. R. McNicol

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. R. McNicol

814 Union Center, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 9th day of October

My commission expires September 30, 1959

Darlene May
Darlene May

RECEIVED
OCT 10 1958
STATE CORPORATION COMMISSION

Notary Public.
OCT 10 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 14 T 31 R 5 W
BOOK PAGE 135 LINE 36



ROTARY DRILLING LOG

OPERATOR: W. J. Coppinger
Schrock No. 1
C NW NW Sec. 14-31-18W,
Comanche County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 9/15/58
COMP: 10/6/58

Remarks: Set 8-5/8" surface casing
at 382' cemented with 200
sacks cement.

Formations:

Clay, Sand & Shale	280'
Lime	290'
Lime & Shale	602'
Red Rock & Shale	915'
Shale & Shells	1600'
Shale & Lime Streaks	1750'
Shale & Lime	2017'
Shale & Lime Streaks	2215'
Shale & Lime	2355'
Lime & Shale	2443'
Lime	2520'
Lime & Shale	2615'
Lime	2839'
Lime & Shale Streaks	3049'
Shale & Lime	3180'
Lime & Shale	3280'
Shale & Lime Streaks	3381'
Shale & Lime	3485'
Lime	3632'
Lime & Shale	3876'
Lime	3980'
Lime & Shale	4150'
Lime	4222'
Lime & Shale	4318'
Lime	5232'
Rotary Total Depth (D&A)	5232'

We certify the above log is true
and correct to the best of our
knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

RECEIVED
STATE POLICE COMMISSION

OCT 10 1958
10-10-58
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING			
FILE	SEC 14	T 31	R 18W
BOOK	PAGE 135	LINE 30	