

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,308-0000

LEASE NAME IRENE LARRISON

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 8 TWP. 30 RGE. 13 (E) or (W)

LEASE OPERATOR Woolsey Petroleum Corporation

COUNTY Barber

ADDRESS 107 N. Market, Suite 600 Wichita, Ks 67202

PHONE#(316) 267-4379 OPERATORS LICENSE NO. _____

Date Well Completed 8-2-90

Character of Well D & A

Plugging Commenced 8-3-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-3-90

The plugging proposal was approved on August 3, 1990 (date)

by Carl Morris (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4770

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				13 3/8	101	NONE
				8 5/8	1016	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Filled hole w/heavy mud: 1st plug from 1030 to 790 w/60 sx; 2nd plug from 40' to surface w/10 sx. 15 sx in rathole, 10 sx in mousehole. All cement 60/40 pozmix 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main #801 Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Abercrombie Drilling, Inc.

STATE OF _____ COUNTY OF _____, ss.

Jack K. Wharton

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) _____

SUBSCRIBED AND SWORN TO before me this 13th. day of August, 19 90

Angela Woodard
Notary Public

My Commission Expires: 3-20-93



15-007-22308-0000

Woolsey Petroleum Corporation
107 N. Market, Suite 600
Wichita, KS 67202

IRENE LARRISON #1
NE-SW Sec. 8-30S-13W
Barber County, Kansas

CONDUCTOR: 13 3/8" 48# casing set @ 101'
SURFACE: 8 5/8" set at 1016
CONTRACTOR: Abercrombie Drilling, Inc.

DRILLERS WELL LOG

		<u>7-23-90</u>
0 - 38'	Top soil & sand	
		<u>7-24-90</u>
38' - 105'	Sand & shale	
105' - 345'	Sand	
345' - 404'	Sand & shale	
		<u>7-25-90</u>
404' - 1023'	Sand & shale	
1023' - 1060'	Shale	
		<u>7-26-90</u>
1060' - 1995'	Sand & shale	
1995' - 2265'	Shale	
		<u>7-27-90</u>
2265' - 3165'	Shale	
		<u>7-28-90</u>
3165' - 3850'	Lime & shale	
		<u>7-29-90</u>
3850' - 4308'	Lime & shale	
		<u>7-30-90</u>
4308' - 4420'	Lime & shale	
		<u>7-31-90</u>
4420' - 4488'	Lime & shale	
4488' - 4492'	Lime	
4492' - 4530'	Lime & shale	
		<u>8-1-90</u>
4530' - 4623'	Lime & shale	
		<u>8-2-90</u>
4623' - 4770'	Lime & shale	

RECEIVED
STATE CORPORATION COMMISSION

AUG 14 1990
8-14-90
CONSERVATION DIVISION
Wichita, Kansas