


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Comanche County, Sec. 11 Twp. 32S Rge. 17W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines



Locate well correctly on above
Section Plot

C NE SW

Lease Owner The Maurice L. Brown Company & KRM Pet. Corp.

Lease Name York Well No. 1

Office Address 200 Sutton Place, Wichita, KS 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed 1/30/78 19

Application for plugging filed 1/30/78 19

Application for plugging approved 1/30/78 19

Plugging commenced 1/30/78 19

Plugging completed 1/30/78 19

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production

19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Owens

Producing formation Depth to top Bottom Total Depth of Well 5304'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	158'	13"	Yes	
	Surface		758'	8 5/8"	Yes	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

1st Plug @ 600' w/35 sx.

2nd Plug @ 40' w/12 sx.

Plug Rathole w/3 sx.

RECEIVED
STATE CORPORATION COMMISSION

MAR 06 1978

3-6-78
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert-Jones, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Vern Haselhorst (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Vern Haselhorst


200 Sutton Place, Wichita, Ks. 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 78

Marjorie P. Jennings
Notary Public.

My commission expires July 29, 1981
Appointment



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

York #1
 C NE SW Sec 11-32S-17W
 Comanche County Kansas

Commenced: 1-14-78

Completed: 1-30-78

OPERATOR: MAURICE L. BROWN CO.

Depth From	to	Formation	Remarks
0	162	Surface Clay-Sand	Ran 8 jts of 46# 13"
162	220	Redbed	csg set @ 158' Cemented
220	850	Redbed-Sand-Shale	w/200 sks Common 2% Gel
850	2125	Shale	3% CC 1/4# Flocele per Sack
2125	2485	Shale-lime	Plug Down @ 12:30 A.M.
2485	2945	Lime-Shale	1-15-78
2945	3165	Shale-Lime	
3165	4666	Lime-Shale	Ran 18 jts of 8 5/8" 24#
4666	4902	Lime	csg set @ 758' Cemented
4902	4972	Lime-Shert	w/300 sks Howcolite 3% CC
4972	5039	Lime-Shale-Chert	1/4# Flocele - 150 sks
5039	5097	Lime-Shale-Stks	Class A 3% CC - 1/4#
5097	5148	Lime	Flocele PD @ 5:45 a.m.
5148	5160	Lime-Chalk	1-16-78
5160	5300 - TD	Lime	DRY & ABANDONED

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 06 1978
 3-6-78
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Subscribed and sworn to before me this 3rd day of February, 1978.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

ELIZABETH J. EDWARDS
 STATE OF KANSAS
 NOTARY PUBLIC
 COMM. EXPIRES FEBRUARY 6, 1979