

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-033-20,754-0000

LEASE NAME Sheramn "A"

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 18TWP. 31 RGE. 18 (E) or (W)

COUNTY Comanche

LEASE OPERATOR Haven Energy Corp.

ADDRESS 7310 East Kellogg Wichita, KS 67207-1695

PHONE#(316) 698-4407 OPERATORS LICENSE NO. 3646

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 8-13-89

Plugging Commenced 8-13-89

Plugging Completed 8-13-89

The plugging proposal was approved on 8-8-89 (date)

by Mr. Lacey (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator if not, Is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 5900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Top Plug: @1140' w/50 sacks cement thru drill pipe

Next Plug: @ 630' w/40 " " " " "

Top Plug: @ 40' w/ 10 " " " " "

15 sacks cement in Rat Hole 10 sacks in Mouse Hole 10 sacks water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

RECEIVED
 STATE CORPORATION COMMISSION
8-17-89
 AUG 17 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lobo Drilling Co.


STATE OF Kansas COUNTY OF Barton, ss.

CONSERVATION DIVISION
 Wichita, Kansas

Ervin Neighbors (Employee of Operator) or XXXXXXXXXX of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530



SUBSCRIBED AND SWORN TO before me this 16 day of August, 19 89

Dorothy M. Hague
 Notary Public

Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: July 31, 1989
DATE COMPLETED: August 13, 1989

Haven Energy Corp.
SHERMAN "A" #1
C NE SE
SEC. 18, T31S, R18W
COMANCHE COUNTY, KS.

0 - 100' Surface Soil, Shale, Sand
100 - 250' Sand
250 - 355' Shale
355 - 2492' Clay, Shale
2492 - 2982' Lime & Shale
2982 - 3870' Shale & Lime
3870 - 5900' Lime
5900' RTD

ELEVATION\$ 2207' K.B.

Surface Pipe: Set used
8-5/8", 257 pipe @609'
w/280 sacks 60/40 pozmix
1" top 60' w/100 sacks
60/40 pozmix 2% gel 3% cc.
Basket @520' & 90' w/baffle
ring in collar.


AFFIDAVIT

STATE OF KANSAS
COUNTY OF BARTON) 28

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 16 day of August 1989.



Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1989
8-17-89
CONSERVATION DIVISION
Wichita, Kansas