

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-033-20,750-0000

LEASE NAME United Methodist

TYPE OR PRINT

NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4670 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 19 TWP. 31 RGE. 18 (E) or (W)

COUNTY Comanche

LEASE OPERATOR Haven Energy Corporation

ADDRESS 7310 East Kellogg Wichita, KS 67207-1695

PHONE#(316) 689-4407 OPERATORS LICENSE NO. 3646

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 7-28-89

Plugging Commenced 7-28-89

Plugging Completed 7-28-89

The plugging proposal was approved on 7-24-89 (date)

by Mr. Goodrow (KCC District Agent's Name).
 to be filed

Is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 5410

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @ 1140' w/50 sacks cement thru drill pipe

Next Plug: @ 620' w/40 sacks " " " "

Top Plug: @ 40' w/10 sacks " " " "

10 sacks in Rat Hole 10 sacks in Mouse Hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Co. License No. 5864
 STATE OF KANSAS

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss. Ervin Neighbors
 CONSOLE NOTARY DIVISION
 Wichita, Kansas

Ervin Neighbors (Employee of Operator) or ~~Operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 31 day of July, 19 89

Barclay M. Hague
 Notary Public

My Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: July 18, 1989
 DATE COMPLETED: July 28, 1989

Haven Energy Corp.
UNITED METHODIST #1
 50' N of C NE NW
 Sec. 19, 31S, R18W
 Comanche County, Ks.

0 - 300' Surface soil, Sand
 300 - 608' Clay & Shale
 608 - 1450' Clay, Shale, Lime Streaks
 1450 - 1900' Shale
 1900 - 2622' Shale & Lime
 2622 - 4595' Lime
 4595 - 4755' Lime & Shale
 4755 - 5410' Lime
 5410' RTD

ELEVATION: 2186 K.B.

SURFACE PIPE: Set used
 8-5/8", 25# pipe @606'
 w/325 sacks 60/40 pozmix
 2% gel 2% cc.


A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) SS

ERVIN NEIGHBORS OF LAWFUL AGE, DOES SWEAR AND STATE THAT THE FACTS AND
 STATEMENTS HEREIN ARE TRUE AND CORRECT TO THE BEST OF HIS KNOWLEDGE.

Ervin Neighbors

Subscribed and sworn to before me this 31 day of August 1989.



Dorothy M. Hagge
 Notary Public