

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-033-20,035-0000

LEASE NAME Boisseau

WELL NUMBER #1

4620 Ft. from S Section Line

660 Ft. from E Section Line

SEC 22 TWP. 31 RGE. 18 (E) or (W)

COUNTY Comanche

Date Well Completed _____

Plugging Commenced 1-3-89

Plugging Completed 1-10-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Rockhold Engineering, Inc.

ADDRESS Box 698, Great Bend, Kansas 67530

PHONE# 316-792-2506 OPERATORS LICENSE NO. 5111

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on January 10, 1989 (date)

by Dan Goodrow (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom T.D. 5110'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORD | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	534'	None
				4-1/2"	5108'	601.25'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 25 sacks cement thru the tubing at 5000'. Pulled 18 joints of 4-1/2" csg. B.J. Titan plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 120 sacks 60/40 pozmix with 6% gel. Maximum pressure was 300 psi and shut in 200 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rockhold Engineering, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 11th day of January, 1989

Jon M. Leatherman
Notary Public

My Commission Expires _____

