

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Comanche SEC. 25 TWP. 32S RGE. 16W E/W  
Location as in quarters or footage from lines:  
990' FNL and 330' FEL


Locate Well  
correctly on above  
Section Platt.

Lease Owner Wells Energy Corporation  
Lease Name Unruh #1 Well No. \_\_\_\_\_  
Office Address Suite 454, 700 S. Colorado Blvd., Denver, Co. 80222  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 6/3/81  
Plugging completed 6/8/81  
Reason for abandonment of well or producing formation \_\_\_\_\_  
Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4788'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	488	None
				4 1/2"	4787'	4038'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Moved in. Made bottom hole plug back with sand to 4700'. Mixed and ran 4 sacks cement. Pulled 24" tension. Made shot at 4155' - not loose. Made shot at 4030' and pulled a total of 96 joints. Squeezed hole with 15 sacks gel, 6 sacks hulls and 10 sacks gel. Released plug and displaced with 165 sacks 50/50 pos 4% gel 3% cc. Plugging complete.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KELSO CASING PULLING

RECEIVED  
STATE CORPORATION COMMISSION

JUN 10 1981

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 1981

My Commission expires:



Joan Kelso  
Notary Public.