

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
203 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-033-20,167-00-00

LEASE NAME Burt

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

1980 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 36 TWP. 31 RGE. 19 (E) or (W)

COUNTY Comanche

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-19-90

Plugging Completed 3-9-90

LEASE OPERATOR Joe A. Amos (Lee Banks Oil)

ADDRESS 111 W. Douglas, #725, Wichita, Ks. 67202

PHONE# (316) 522-2724 OPERATORS LICENSE NO. 5142

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 9, 1990 (date)

by Steve Durrant (KCC District Agent's Name).

Is ACO-1 filled? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 5173'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	388'	None
				4-1/2"	5173'	3,172.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4240' and 4 sacks cement. Shot casing at 4100', 3800', 3500', 3200'. Pulled 95 jts. of 4-1/2" casing. Allied plugged well with 300# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls, released plug and pumped 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe A. Amos

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold  
Box 698, Gt. Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 12th day of March, 1990

MAR 14 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Commission Expires \_\_\_\_\_



IONA M. LEATHERMAN  
Barton County, Kansas

My Appt. Exp. 4-26-91

Iona M. Leatherman  
Notary Public

15-033-20167-00-00

**Banko Oil Co.**

**Burt #1  
C NE SE Sec. 36-31S-19W  
Comanche County, Kansas**

**Contractor: D. R. Lauck Oil Company, Inc.  
301 S. Broadway  
Wichita, Kansas 67202**

**Commenced: December 22, 1974  
Completed: January 11, 1975**

**Drillers Log**

Shale & Sand Streaks	140
Sand	260
Shale	765
Shale & Shells	1560
Shale & Lime Shells	2100
Lime & Shale	2415
Lime	3265
Shale	3420
Shale & Lime	3560
Lime	3675
Shale & Lime	3925
Lime	4030
Shale & Lime	4160
Lime	4405
Lime & Shale	4525
Lime	5174 RTD

STATE OF KANSAS  
RECEIVED  
DEC 26 1989  
Conservation Division  
Wichita, Kansas

12-26-1989