

To: 1 020520
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-033-20,860-0000 2310
SW NE SW, SEC. 9, T 32 S, R 17 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5131
Operator: Thunderbird Drilling, Inc.
Name & Address: P.O. Box 780407
Wichita, KS 67278

1650 feet from S section line
3630 feet from E section line
Lease Name Hackney "B" Well # 1
County Comanche
Well Total Depth 5249 170.59 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 610

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Brandt Drilling Company, Inc. License Number 5840
Address 200 W. Douglas, Ste. 700, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 7 Month: 10 Year: 19 92

Plugging proposal received from Merlin Freeman
(company name) Brandt Drilling Company, Inc. (phone) 316-267-4335

were: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 1050' with 50 sx cement,
2nd plug at 640' with 50 sx cement,
3rd plug at 40', with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: _____ Day: 7 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement,
2nd plug at 640' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel By Allied.

(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
10-19-92
OCT 19 1992

INVOICED
(did not) observe this plugging.

DATE 11-16-92

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 36761

EFFECTIVE DATE: 9-30-92
DISTRICT # 1
SEAT Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL

033 - 20860
019 - 24280
FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date Sep 23 1992
month day year

Spot SW NE SW Sec 9 Twp 32 S, Rg 17 East West

OPERATOR: License # 5131
Name: Thunderbird Drilling, Inc.
Address: P. O. Box 780407
City/State/Zip: Wichita, KS 67278
Contact Person: Burke B. Krueger
Phone: 316-625-1441

1650 feet from South / North line of Section
 3630 feet from East / West line of Section
IS SECTION REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)

County: Comanche
Lease Name: Hackney "B" Well #: 1
Field Name: Wildcat

CONTRACTOR: License # 5840
Name: Brandt Drilling Co., Inc.

Is this a Propped/Spaced Field? yes no

Target Formation(s): Mississippian

Nearest lease or unit boundary: 990

Ground Surface Elevation: 2090 Est. feet HSL

Water well within one-quarter mile: yes no

Public water supply well within one mile: yes no

Depth to bottom of fresh water: 180

Depth to bottom of usable water: 245 250

Surface Pipe by Alternate: 1 2

Length of Surface Pipe Planned to be set: 600

Length of Conductor pipe required: None

Projected Total Depth: 5250

Formation at Total Depth: Mississippian

Water Source for Drilling Operations:

well farm pond other

DWR Permit #: _____

Will Cores Be Taken? yes no

If yes, proposed zone: _____

Well Drilled For: Well Class: Type Equipment:
 Oil Enh Rec Infield Mud Rotary
 Gas Storage Pool Ext. Air Rotary
 OWWG Disposal Wildcat Cable
 Seismic; # of Holes Other

If OWWG, old well information as follows:

Operator: _____

Well Name: _____

Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes no

If yes, true vertical depth: _____

Bottom Hole Location: _____

Expires 3-24-92 AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Merlin Freeman
SPUD DATE 9-25-92 INIT. R.C.
LENGTH SURFACE PLANNED 600'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbbls. when done bbbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 3/4 @ 610 CONDUCTOR
ANHYDRITE T- B- ELEVATION

TD 5249 FORMATION _____

RAN PIPE @ SX DV TOOL SX ALT II DONE Y N

Arbuckle Plug @ _____ Ft. W/ SX

Hug./Council @ _____ Ft. W/ SX

Anhydrite Base @ 1050 Ft. W/ 50 SX

1/2 Base Anyh. @ _____ Ft. W/ SX

1/2, 1/2 Plug @ _____ Ft. W/ SX

Bottom Surface @ 640 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 5 SX MOUSE HOLE W/10 SX

WATER WELL SX (Irr. Well _____ Pond _____)
Hauling _____

TECHNICIAN _____ DATE _____

TYPE OF CEMENT 6044 legs jet

STARTING TIME 10:15 (AM/PM) DATE 10/19/92

COMPLETION TIME 12:07 (AM/PM) DATE 10/19/92

CEMENT COMPANY Phillips

RECEIVED
OCT 19 1992
CONSERVATION DIVISION
Wichita, Kansas
DATE 10/19/92
DATE 10/19/92