

1070070

TO:

API NUMBER 15-033-20,940-00-00

5-21

STATE CORPORATION COMMISSION

W/2 W/2 NE, SEC. 8, T 32 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION

1320 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRASS WELL # 1-8

TECHNICIAN'S PLUGGING REPORT

COUNTY COMANCHE

OPERATOR LICENSE # 5293

WELL TOTAL DEPTH 6088' ^{197.86} FEET

OPERATOR: HELMERICH & PAYNE, INC

PRODUCTION CSG: SIZE 5 1/2" FEET 6068'

NAME AND 2606 FLEMING

SURFACE CASING: SIZE 8 5/8" FEET 698'

ADDRESS GARDEN CITY, KANSAS 67846

CONDUCTOR: SIZE 20" FEET 40'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS 107 W. Fowler, P.O. Box 187, Medicine Lodge, Kansas 67104

COMPANY TO PLUG AT: HOUR: 14:30 DAY: 21 MONTH: 5 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) (316) 886-5665

WERE: PBTD 6019', Perfs at 5776-5788' CIBP @ 5740', 5082-5096' CIBP @ 5064', 5035-5043'

CIBP @ 4500', 4400-4408'; 1st plug sand back to 4320' w/5sxs cement on top

2nd plug pump 300 # hulls, 10 sxs gel, 50 sxs cement, 10 sxs gel, 100# hulls, 8 5/8"

Wiper plug, 100 sxs cement

PLUGGING PROPOSAL RECEIVED BY Scott Alberg

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 15:15 DAY: 21 MONTH: 5 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sand back to 4320' w/5 sxs cement on top

2nd plug pump 300# hulls, 10 sxs gel, 50 sxs cement, 10 sxs gel, 100# hulls, 8 5/8"

Wiper plug, 100 sxs cement.

RECEIVED
KANSAS CORPORATION COMMISSION
06-03-1998
JUN 03 1998

Maximum Pressure 500#, Shut In Pressure 200#.

REMARKS: Used 60/40 Poz 6% Gel by Allied Cementing, Recovered 3700' of 5 1/2" casing.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

[Signature]
(TECHNICIAN)

FORM CP-2/3

[Handwritten mark]

INVOICED

DATE 6-8-98

INV. NO. 50685