

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25656-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 16-16S-13W
2283 feet from S Section Line, 1605 feet from E Section Line
Lease Name: KRUG / ALLAN Well #: 1
County: BARTON Total Vertical Depth: 3500 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3490	2100	175 SX
SURF	8.625	452		190 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2014 10:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Revd. from: CHRIS SCHOENHOFER Company: CHARTER ENERGY LLC Phone: (620) 793-9090

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2014 10:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

04/14/2014- Sanded off bottom to 3290'.
04/15/2014- Spotted 5 sx cement on sand. Cut pipe at 2100'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 840' and pumped 50 sx cement w/100 # hulls. Pulled casing to 550' and pumped 85 sx cement. Cement circulated. Pulled casing out of hole. Topped off and filled cellar w/30 sx cement.

GPS: 38.65860 -098.76246

Perfs:

Top	Bot	Thru	Comments
3434	3437		
3416	3420		
3410	3412		

KCC WICHITA

APR 23 2014

RECEIVED

Remarks: QUALITY CEMENTING TICKET # 411

Plugged through: CSG

District: 04

Signed: Ray Dinkel
4/24/14 (TECHNICIAN)

CM

APR 16 2014