

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20326-00-00
Spot: SESENWNW Sec/Twnshp/Rge: 15-25S-31W
4125 feet from S Section Line, 4125 feet from E Section Line
Lease Name: BEACH-CORLEY Well #: 1-15
County: FINNEY Total Vertical Depth: 2700 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2699	0	WITH 650 SX CMT
SURF	8.625	369		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2014 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PUMP 260 SX CMT WITH 250# HULLS IN FIRST PART DOWN 5 1/2" CASING. USE 40 SX CMT FOR ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2014 11:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING WITH CMT FROM 2547' TO 0' USING 255 SX CMT & 250# HULLS. PRESSURE TO 450#. HOLDING. PUMP 35 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2537	2547		

KCC WICHITA
APR 21 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE.** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: CSG

District: 01

RECEIVED

APR 15 2014

KCC DODGE CITY

Signed

Ken Jehlik
4/24/14

(TECHNICIAN)

RCW