

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21363-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 11-20S-16W
360 feet from S Section Line, 738 feet from E Section Line
Lease Name: BLAKE Well #: 1
County: PAWNEE Total Vertical Depth: 3880 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: 114 NORTH MAIN P.O. BOX 486
ELLINWOOD, KS 67526

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 3879 | 1993 | WITH 125 SX CMT |
| SURF | 8.625 | 1054 | | WITH 375 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2014 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3750' WITH 5 SX CMT. PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2014 11:00 AM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

Perfs:

SAND TO 3750' WITH 5 SX CMT. 1ST PLUG AT 1080' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA

APR 21 2014

RECEIVED

District: 01

Signed

Nathan Willis
2/24/14
(TECHNICIAN)

RECEIVED

APR 15 2014

KCC DODGE CITY

DNF