

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22033-00-00
Spot: NENWSE Sec/Twnshp/Rge: 26-15S-14W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HOFFMAN Well #: 5
County: RUSSELL Total Vertical Depth: 3350 feet

Operator License No.: 33830
Op Name: HEWITT ENERGY GROUP, INC.
Address: 175 S. MAIN ST., STE 900
SALT LAKE CITY, UT 84111

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3300		
SURF	8.625	240		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2014 2:30 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: DENNIS KLIMA Company: HEWITT ENERGY GROUP INC. Phone: (620) 786-1031

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/14/2014 6:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3100' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1850' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 600' and pumped 75 sx cement. Cement circulated to surface. Pulled tubing out of hole. Hooked on to casing and pumped 15 sx cement at 350 psi to shut in. Hooked to braden head and pumped 30 sx cement at 300 psi. Holes in the casing found early on a work over.

GPS: 38.71773 -098.84349

Remarks: ALLIED CEMENTING TICKET # 55218

Plugged through: TBG

KCC WICHITA

APR 23 2014

RECEIVED

District: 04

Signed Ray A. Dinkel
4/24/14 (TECHNICIAN)

CM

APR 16 2014