

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-10116-00-01
Spot: NWSENE Sec/Twnshp/Rge: 19-30S-33W
1979 feet from S Section Line, 3288 feet from E Section Line
Lease Name: SWLVLU Well #: 39
County: HASKELL Total Vertical Depth: 4850 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4700	1182	WITH 175 SX CMT
SURF	8.625	721		WITH 650 SX CMT

Well Type: EOR UIC Docket No: E30036.20 Date/Time to Plug: 04/03/2014 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP W/ 2 SX CMT OR 20 SX CMT AT 2700' TO 3000'. PERFORATE 4 HOLES OR SPLIT COLLAR AT 1760'. SPOT 40 SX CMT THRU TBG. CUT & PULL CASING. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2014 12:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

4/3/14: TOP OF STUCK TBG FISH @ 3017'. GLORIETTA SAND FILL UP AT 2661'. PUMP 20 SX CMT AT 2614' FOR BOTTOM PLUG. BLOW A COLLAR AT 1760'. RUN TBG TO 1760' & SPOT 40 SX CMT. 4/4/14: TAG TOC IN 5 1/2" @ 1482'. 10 SX CMT WENT OUT SPLIT. 30 SX CMT STAYED IN 5 1/2" CASING. SHOT OFF CASING AT 1182'. PULL TO 750'. PUMP 50 SX CMT AT 750'. LOST CIRCULATION. TOO H W/ CASING. 4/7/14: TAGGED TOC @ 572'. LOADED HOLE. SPOT 10 SX CMT PLUG AT 40' TO 0'.

Perfs:

Top	Bot	Thru	Comments
4579	4581		
4157	4159		
4156	4164		
4136	4138		
4131	4133		

KCC WICHITA
APR 21 2014
RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
4/8/14 (TECHNICIAN)

RECEIVED

APR - 9 2014

KCC DODGE CITY

cc to UIC 4/28/14

Form CP-2/3

ADW