

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-22071-00-01
Spot: SWNESENW Sec/Twnshp/Rge: 12-34S-33W
3315 feet from S Section Line, 3274 feet from E Section Line
Lease Name: HATCHER Well #: 1-12
County: SEWARD Total Vertical Depth: 6550 feet

Operator License No.: 34745
Op Name: GLOBE ENERGY SERVICES LLC
Address: 1015 N. COLLEGE AVE. PO BOX 255
SNYDER, TX 79550

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1800		
CIBP		3335		WITH 2 SX CMT
DVT	5.5	3345		
PROD	5.5	6350	0	
SURF	8.625	1720		WITH 600 SX CMT

Well Type: SWD UIC Docket No: D30331.0 Date/Time to Plug: 04/10/2014 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RUFUS WILKES Company: GLOBE ENERGY Phone: (325) 207-7799

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2014 8:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

****WELL HAS MULTIPLE CASING LEAKS ABOVE & BELOW THE DV TOOL.** PUMP 100 SX CMT WITH 100# HULLS AT 5926'. CIBP WITH 2 SX CMT AT 3335'. CIBP @ 1800'. PERFORATE 4 HOLES AT 1746'. RUN TBG & PACKER TO 1390' WITH TAIL PIPE TO 1711'. SPOT 75 SX CMT WITH HULLS IN THE LAST 20 SX CMT. PRESSURE INCREASED FROM 150# TO 600#. FULL CIRCULATION. TOOH W/ TBG & PACKER. PERFORATE 4 HOLES @ 550'. CIRCULATE CMT TO SURFACE USING 205 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.**

Perfs:

Top	Bot	Thru	Comments
2716	2729		

KCC WICHITA

APR 21 2014

RECEIVED

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

APR 15 2014

KCC DODGE CITY

Signed

Ken Jehlik
4/23/14
cc to MC 4/23/14

(TECHNICIAN)

mm