

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20614-00-01
Spot: NESWSENE Sec/Twnshp/Rge: 2-31S-35W
3263 feet from S Section Line, 805 feet from E Section Line
Lease Name: CULLISON C Well #: 2-2
County: STEVENS Total Vertical Depth: 5900 feet

Operator License No.: 34738
Op Name: CULLISON, JIMMY I.
Address: C/O JW CULLISON PO BOX 367
SATANTA, KS 67870

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1550		
CIBP		1650		
PROD	4.5	5900	0	WITH 325 SX CMT
SURF	8.625	1650		

Well Type: SWD UIC Docket No: D25029.0 Date/Time to Plug: 04/01/2014 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: Pull tbg & PKR. RU down 4.5" casing. Mix & pump 150 sks Class "C" cement w/200lbs cotton seed hulls & leave full to surface. RU down 8.625" casing, fill w/5-20 sks cement & pressure to 300 psi

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
Date/Time Plugging Completed: 04/01/2014 10:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

CIBP @ 1550'. PUMP 70 SX CMT WITH 200# HULLS, THEN 100 SX CMT DOWN 4 1/2 CASING. CHECK 8 5/8" X 4 1/2" ANNULUS WITH 20 SX CMT. PRESSURE TO 300#.

Perfs:

Top	Bot	Thru	Comments
1260	1290		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

KCC WICHITA
APR 21 2014
RECEIVED

District: 01

RECEIVED

APR 15 2014

KCC DODGE CITY

Signed

(TECHNICIAN)