

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20405-00-00
Spot: SESW Sec/Twnshp/Rge: 28-2S-31W
4620 feet from N Section Line, 1980 feet from W Section Line
Lease Name: HAFNER A Well #: 1
County: RAWLINS Total Vertical Depth: 4441 feet

Operator License No.: 31100
Op Name: ROBUCK PETROLEUM, LLC
Address: PO BOX 1896
EDWARDS, CO 81632

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4128		150 SX
SURF	8.625	415		275 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2014 3:30 PM
Plug Co. License No.: 31660 Plug Co. Name: ROBUCK, DON E. DBA ENERGY SEARCH OPERATING COMPANY
Proposal Rcvd. from: BRETT ROBUCK Company: ROBUCK PETROLEUM CO. LLC. Phone: (308) 345-7200

Proposed Plugging Method: 8 5/8" surface pipe set at 415' w/275 sx cement. 4 1/2" production casing set at 4128" w/150 sx cement. TD 4441', PBTD 4098'. Perforations: 3879' - 3885', 3902' - 3904' and 3959' - 3963'. Casing reported to be in poor condition.
Ordered 450 sx 60/40 pozmix 4% gel cement w/750 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2014 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2700', 2100' and 390'.
04/10/2014- Ran tubing to 3888' and pumped 90 sx cement w/250 # hulls. Problems with cement pump truck. Pulled tubing to 1000' and shut down for the day.
04/11/2014- Tagged cement plug at 2645' with tubing. Pulled tubing to 2615' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 1510' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 408' and pumped 175 sx cement. Circulated cement to surface from 8 5/8" surface casing and 4 1/2" production casing. Pulled tubing to surface and topped off w/25 sx cement.

GPS: 39.84481N -100.80779W

Perfs:

Top	Bot	Thru	Comments
3959	3962		
3901	3904		
3879	3885		

KCC WICHITA

APR 23 2014

RECEIVED

Remarks: GLOBAL CEMENT TICKET # 1293

Plugged through: TBG

District: 04

Signed Darrel Dipman
4/28/14 (TECHNICIAN)

CM

APR 16 2014