

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20859-00-02  
Spot: SWSWNESE Sec/Twnshp/Rge: 23-8S-17W  
1610 feet from S Section Line, 1094 feet from E Section Line  
Lease Name: LEROCK Well #: 1  
County: ROOKS Total Vertical Depth: 3483 feet

Operator License No.: 33315  
Op Name: MAR-LOU OIL CO., LLC  
Address: PO BOX 218  
WILSON, KS 67490

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3465		200 SX
SURF	8.625	290		170 SX

Well Type: EOR UIC Docket No: E27241.1 Date/Time to Plug: 04/03/2014 8:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JEFF CRAWFORD Company: JEFF'S OILWELL SUPERVISION Phone: (785) 885-8013

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 6 sx gel and 500 # hulls.  
Squeezed at 908' - 940' w/200 sx cement.  
Squeezed at 2134' - 2520' w/450 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/03/2014 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3275' and pumped 6 sx gel followed by 50 sx cement and 100 # hulls. Pulled tubing to 1855' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 907' and pumped 90 sx cement to circulate cement to surface. Pulled all tubing. Hooked to 4 1/2" casing and pumped 15 sx cement. Shut in pressure 300 psi. Hooked to 8 5/8" x 4 1/2" annulus and pumped 25 sx cement. 100 psi shut in pressure.

GPS: 39.34051N -099.17950W

Perfs:

Top	Bot	Thru	Comments
3112	3356		

KCC WICHITA

Remarks: SWIFT TICKET # 25416

APR 23 2014

Plugged through: TBG

RECEIVED

District: 04

Signed

Pat Bedore  
4/24/14 (TECHNICIAN)  
cc to UIC 4/23/14

CM

APR 17 2014