

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
FEB 11 2002
2-11-02
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-007-22,217 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Woolsey Petroleum Corp. KCC LICENSE # 5506
(owner/company name) (operator's)

ADDRESS 125 N. Market CITY Wichita

STATE KS ZIP CODE 67202 CONTACT PHONE # (620) 886-5606 ext. 27

LEASE Lambert WELL# B-1 SEC. 8 T. 30 R. 13 (East/West)

SPOT LOCATION/QQQQ COUNTY Barber

660 FEET (in exact footage) FROM S (N) (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL X GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE 13 3/8" SET AT 135' CEMENTED WITH 180 SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1064' CEMENTED WITH 450 SACKS

PRODUCTION CASING SIZE 5 1/2" SET AT 4734' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4674' to 84' - CIBP @ 4668' - 4630' to 50'

ELEVATION 1939' T.D. 4730' PBTD 4694' ANHYDRITE DEPTH 1060'
(G.L. (K.B)) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4580', spot 5 sax cmt w/ bailer, Cut Csg and Plug as follows through 5 1/2" casing: @ 1100' pump 15 gel & 50sax cement, at 400', 40 sax cement & @ 40' cement to surface with 10 sax. Use 60/40 poz + 6% gel.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? X IS ACO-1 FILED? yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Carl W. Durr PHONE# (620) 886-5606 ext. 27

ADDRESS Medicine Lodge City/State Kansas

PLUGGING CONTRACTOR Clarke Corp. KCC LICENSE # 5105
(company name) (contractor's)

ADDRESS Medicine Lodge, KS PHONE # (620) 886-5665

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/8/2002 AUTHORIZED OPERATOR/AGENT: Carl W. Durr
(signature)



Kansas Corporation Commission

Bill Graves, Governor John Wine, Chair Cynthia L. Claus, Commissioner Brian J. Moline, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Woolsey Petroleum Corporation
125 N. Market, Suite 1000
Wichita, KS 67202-1775

February 20, 2002

Re: DON LAMBERT 1-B #OWWO
API 15-007-22217-00-01
NENW-8-30S-13W, 4620 FSL 3300 FEL
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in black ink, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(316) 225-8888