

1 040555

8-2
API NUMBER 19- 033-20,772-~~000~~ 20P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW NE, SEC. 8, T. 32 S, R. 17 W/EX
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9354

Lease Name Zeigler Well # 1

Operator: Central Energy Corporation

County Comanche 170.62

Name & Address P.O. Box 47590

Well Total Depth 5250 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 596

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 2 Month: 8 Year: 19 91

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 5249' w/100 sx cement, Perfs at 5142-56'

1st plug sand back to 5090' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 2 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 5092' and dumped 5 sx cement on top of

sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2705.35' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 8-27-91
INV. NO. 32839

RECEIVED
STATE CORPORATION COMMISSION
observe this plugging.
AUG 07 1991
8-7-91
CONSERVATION DIVISION
Wichita, Kansas

Signed *Steve Pfeifer* (TECHNICIAN)