

To: 1 120208
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-10
API NUMBER 15-033-20,035-0000
C NE NE, SEC. 22, T 31 S, R 18 W/E
4620 feet from S section line
660. feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5111
Operator: Rockhold Engineering
Name & Address Box 698
Great Bend, KS 67530

Lease Name Boisseau Well # 1
County Comanche 166.08
Well Total Depth 5110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 534

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 10 Month: 1 Year: 19 89

Plugging proposal received from Deacon Pulley
(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 5108' cemented with 175 sx PBD 5102' Perfs at 5075-83'
1st plug sand back to 5025' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 10 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped into 8 5/8" surface casing with 500 lbs. hulls,
20 sx gel, released 8 5/8" wiper plug and pumped 170 sx cement.

Pumping pressure 0-300 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
1-17-89
JAN 17 1989

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 60% of 4 1/2" casing.
(If additional description is necessary, use BACK of this report.)

INVOICED

DATE 1-20-89
INV. NO. 23749

Signed Duan Rankin
(TECHNICIAN)