

10-25

To: 1 070602
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,209-0000
E/2 NE SE SEC. 10, T 30 S, R 13 W/E
1980 feet from S section line
535 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3536
Operator: Ramco Oil & Gas Corporation
Name & Address: P.O. Box 99
Belpre, Ohio 45714

Lease Name Eugene R. Lawrenz Well # 1
County Barber 154.86
Well Total Depth 4765 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 258"

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Allen Drilling Company License Number 5418
Address Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12 a.m. Day: 25 Month: 10 Year: 19 88

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1855'

1st plug at 850' with 50 sx cement, RECEIVED

2nd plug at 270' with 40 sx cement, STATE CORPORATION COMMISSION

3rd plug at 40' with 10 sx cement, OCT 27 1988

4th plug to circulate rathole with 15 sx cement. 10-27-88

Plugging Proposal Reviewed by Dan Goodrow (TECHNICIAN)
Conservation Division Wichita, Kansas

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 a.m. Day: 25 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement,

2nd plug at 270' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 10-31-88

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 22851

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... October 13, 1988

API Number 15-007-22,209-0000

OPERATOR: License # 3536
Name Ramco Oil and Gas Corporation
Address P.O. Box 99
City/State/Zip Belpre, Ohio 45714
Contact Person Dave Gocke
Phone (614) 423-9591

APP E/2 NE SE Sec. 10 Twp. 30 S. Rg. 13
1980
535

CONTRACTOR: License # 5418
Name Allen Drilling Company
City/State Great Bend, KS, 67530

(Note: Locate well on Section Plat on reverse side)

Well Drilled For: Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 535 feet
County Barber

Lease Name Eugene R. Lawrenz Well # 1
Ground surface elevation 1855 feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 150
Depth to bottom of usable water 200

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 220

Conductor pipe required N/A
Projected Total Depth 4700 feet

Formation Arbuckle

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
Date 10/05/88 Signature of Operator or Agent Agent

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 220 feet per Alt. 1 X
This Authorization Expires 4-7-89 Approved By LKM 10-7-88

EFFECTIVE DATE: 10-12-88

Spud 10/16/88 Set 258' @ 10 3/4"
Sec. 10 Twp. 30 S. Rg. 13 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth, Formation, and Plugging details. Includes rows for 1st through 5th plugs and Rathole/Mousehole to surface minus 5 feet.

Vertical log section with handwritten entries:
PUSHER Craig Christopher
TD 476.5 FORMATION Top Arb. 473.2 Arbuckle
SURFACE PIPE 10 3/4" @ 258'
ANEHYDRITE ELEVATION 1855'
STARTING TIME & DATE 12:09 A.M. 10-25-88
COMPLETION TIME & DATE 2:30 A.M. 10-25-88
1st PLUG @ 850 FT. W/ 50 SX
2nd PLUG @ 270 FT. W/ 40 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY Halliburton
TECHNICIAN
if more 50' arb 40 s.

RECEIVED STATE CORPORATION COMMISSION
OCT 27 1988
10-27-88
CONSERVATION DIVISION
Wichita, Kansas