

11-28-87

API NUMBER 15-033-20,718-0000

To: 1030892
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW, SEC. 10, T 32 S, R 19 W/R
420 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6196

Lease Name Bird Well # 1A

Operator: Sun Exploration & Production Co.
Name & Address: 525 Central Park Drive
Oklahoma City, OK 73105-1799

County Comanche 202.15
Well Total Depth 6220 feet
Conductor Pipe: Size feet 120
Surface Casing: Size 8 5/8 feet 856

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Sage Drilling Company License Number 5421

Address 202 South St. Francis, Wichita, KS 67202

Company to plug at: Hour: 12 p.m. Day: 28 Month: 11 Year: 19 87

Plugging proposal received from Tom Treece

(company name) Sage Drilling Company (phone) 316-263-6139

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 6100' with 40 sx cement, 2nd plug at 2500' with 40 sx cement,

3rd plug at 1750' with 40 sx cement, 4th plug at 870' with 30 sx cement,

5th plug at 250' with 30 sx cement, 6th plug at 40-0' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement, 8th plug to circulate mousehole with 15 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30 p.m. Day: 28 Month: 11 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 6100' with 40 sx cement,

2nd plug at 2500' with 40 sx cement,

3rd plug at 1750' with 40 sx cement,

4th plug at 870' with 30 sx cement, 5th plug at 250' with 30 sx cement,

6th plug at 40-0' with 10 sx cement, 7th plug to circulate rathole with 15 sx cement,

8th plug to circulate mousehole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (I did not) observe this plugging.

DATE 12-8-87

Signed Steve Durrant (TECHNICIAN)

REV. NO. 19233

11-28 JAN 14 1988

RECEIVED STATE CORPORATION COMMISSION DEC 8 1987 12-8-87 CONSERVATION DIVISION Wichita, Kansas

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 11 month 13 day 87 year

API Number 15-033-20, 718-0000

OPERATOR: License # 6196
Name: SUN EXPLORATION & PRODUCTION COMPANY
Address: 525 Central Park Drive
City/State/Zip: Oklahoma City, OK 73105-1799
Contact Person: Kenney Sifford
Phone: (405) 556-9800

SW SW SW Sec. 10 Twp. 32 S, Rg. 19
420 Ft. from South Line of Section
4950 Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5421
Name: Sage Drilling Company
City/State: 202 South St. Francis, Wichita, KS

Nearest lease or unit boundary line 445 feet
County: Comanche
Lease Name: BIRD Well # 1A
Ground surface elevation 2047 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 X 2
Depth to bottom of fresh water 200
Depth to bottom of usable water 230
Surface pipe planned to be set 850
Projected Total Depth 6200 feet
Formation: ARBUCKLE

Well Drilled For: Well Class: Type Equipment:
Oil SWD Infield X Mud Rotary
X Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.
Date 11-13-87 Signature of Operator or Agent Beverly Kain Title ACCOUNTANT

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 250 feet per Alt.
This Authorization Expires 3-16-88 Approved By
EFFECTIVE DATE 11-21-87

SPUD 11-12-87 (skidded rig) Ran

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth (e.g., 5600-5850), feet depth with, size of, and CLASS A CMT.

Table with 4 columns: Description (e.g., 1st PLUG @ 6100 FT. W/ 40 SX), Formation, Circulation, and Plugging details.

RECEIVED STATE CORPORATION COMMISSION DEC 8 1987 12-8-87 CONSERVATION DIVISION Wichita, Kansas