

8-5-88

To: 1 040144
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING SECTION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API NUMBER 15- 033-01,006-00-01C SW SW, SEC. 14, T 32 S, R 16 W/E660 feet from S section line4620 feet from E section lineLease Name Einsel Well # 1County Comanche 159.74Well Total Depth 4915 feetConductor Pipe: Size feetSize 13 3/8 feet 313STATE CORPORATION COMMISSION
Abandoned Oil Well Gas Well SWD Well D&A XOther well as hereinafter indicated AUG 10 1988 HAD RUN PIPEPlugging Contractor Clarke Corporation License Number 5105Address P.O. Box 187, Medicine Lodge, KS 67101 Wichita, KansasCompany to plug at: Hour: 9:45 a.m. Day: 5 Month: 8 Year: 1988Plugging proposal received from Elmo Morgenstern(company name) Clarke Corporation (phone) 316-886-5665were: 4 1/2" at 4914' PBTB 4870' Perfs at 4811-25'1st plug sand back to 4760' and dump 4 sx cement on top of sand through bailer,2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement. Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)Plugging Operations attended by Agent?: All X Part None Operations Completed: Hour: 10:30 a.m. Day: 5 Month: 8 Year: 1988ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 4 sx cement on top of sand through bailer,2nd plug pumped down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs hulls, and 150 sx cement.Maximum pressure 450 psi and shut in 350 psi.Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 8-11-88INV. NO. 21840Signed Stephen J. Pfeiffer
(TECHNICIAN)FORM CP-2/3
Rev. 01-84