



Operator Name: American Warrior, Inc. Lease Name: Harness Well #: 1-11  
 Sec. 11 Twp. 32 S. R. 19  East  West County: Comanche County, Kansas

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

ORIGINAL

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Heebner	4304'	-2218
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Lansing	4497'	-2411
List All E. Logs Run:		Drum	4694'	-2608
		Swope	4810'	-2724
		BKC	4956'	-2870
		Marmaton	4965'	-2879
		Pawnee	5048'	-2962
		Fort Scott	5088'	-3002
		Miss	5158'	-3072'
		Viola	5771'	-3685

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Conductor		20"		50'			
Conductor	17-1/2"	13-3/8"		300'	ALW Class A	225	3%cc 1/2#floseal
					Class A	100	3%cc 2%gel
Surface	12-1/4"	8-5/8"	28#	654'	ALW Class A	225	3%cc 1/2#floseal
					Class A	100	3%cc 2%gel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
Perforate				
Protect Casing				
Plug Back TD				
Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
	None D/A		

TUBING RECORD	Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
	None	D/A		
Date of First, Resumed Production, SWD or Enhr.	Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity

Disposition of Gas  Vented  Sold  Used on Lease *(If vented, Sumit ACO-18.)*

METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled  Other (Specify)

# ALLIED CEMENTING CO., INC.

5171

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

ORIGINAL

SERVICE POINT:

Med Lodge

DATE <u>2-6-01</u>	SEC. <u>11</u>	TWP. <u>32S</u>	RANGE <u>19W</u>	CALLED OUT <u>7:30 AM</u>	ON LOCATION <u>10:00 AM</u>	JOB START <u>1:45 PM</u>	JOB FINISH <u>5:15 PM</u>
LEASE <u>Harness</u>	WELL # <u>1-11</u>	LOCATION <u>Coldwater kreme</u>		COUNTY <u>Comanche</u>	STATE <u>Ks</u>		
OLD OR <u>(NEW)</u> (Circle one)				<u>1/2 W 1/4 into</u>			

CONTRACTOR <u>Duke #7</u>	OWNER <u>American Warrior</u>
TYPE OF JOB <u>Surface #133</u>	
HOLE SIZE <u>13 3/8</u>	T.D. <u>305</u>
CASING SIZE <u>13 3/8</u>	DEPTH <u>300</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH
TOOL <u>Baffle</u>	DEPTH <u>254.78</u>
PRES. MAX <u>300</u>	MINIMUM <u>100</u>
MEAS. LINE	SHOE JOINT <u>45.22</u>
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>40 1/4 BBLs Fresh H<sub>2</sub>O</u>	

CEMENT			
AMOUNT ORDERED	<u>225 5x 45.35.6 + 3% cc</u>		
	<u>+ 1/4" Flo-seal 250 5x class A 3% cc</u>		
	<u>+ 2% gel</u>		
COMMON	<u>150</u>	@ <u>6.35</u>	<u>952.50</u>
POZMIX		@	
GEL	<u>3</u>	@ <u>9.50</u>	<u>28.50</u>
CHLORIDE	<u>13</u>	@ <u>28.00</u>	<u>364.00</u>
	<u>Akw 225</u>	@ <u>6.00</u>	<u>1350.00</u>
	<u>Flo-Seal 56#</u>	@ <u>1.40</u>	<u>78.40</u>
		@	
		@	
		@	
HANDLING	<u>403</u>	@ <u>1.05</u>	<u>423.15</u>
MILEAGE	<u>403 x 42</u>	<u>.04</u>	<u>677.04</u>

EQUIPMENT	
PUMP TRUCK # <u>359-265</u>	CEMENTER <u>Justin Hart</u>
BULK TRUCK # <u>258-314</u>	HELPER <u>Mark Brungardt</u>
BULK TRUCK #	DRIVER <u>Scott Spriggs</u>
BULK TRUCK #	DRIVER

RECEIVED

TOTAL 3873.54

MAY 14 2002  
5-14-02  
KCC WICHITA

SERVICE

REMARKS:

Pipe on Bottom @ 12:45 Break Circ  
Mix 225 5x 45.35.6 @ 12.8" Mix  
100 5x A 3/2 @ 15.2" Release plug  
Disp 40 1/4 BBLs Bump plug 100# to  
300# shut head in Release press  
circulated Cement  
Top off with 50 5x A 3/2

DEPTH OF JOB	<u>300'</u>		
PUMP TRUCK CHARGE			<u>470.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>42</u>	@ <u>3.00</u>	<u>126.00</u>
PLUG <u>13 3/8 wooden</u>		@ <u>10.00</u>	<u>170.00</u>
		@	
		@	

TOTAL 666.00

CHARGE TO: American Warrior  
STREET P.O. Box 399  
CITY GARDEN CITY STATE KANSAS ZIP 67846

FLOAT EQUIPMENT

<u>13 3/8</u>			
<u>1 - Baffle Plate</u>	@ <u>85.00</u>		<u>85.00</u>
<u>1 - Basket</u>	@ <u>250.00</u>		<u>250.00</u>
	@		
	@		
	@		

TOTAL 335.00

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Kenneth McGuire

TAX \_\_\_\_\_  
TOTAL CHARGE 4872.59  
DISCOUNT 487.26 IF PAID IN 30 DAYS  
4385.33  
KENNETH M'GUIRE  
PRINTED NAME

# ALLIED CEMENTING CO., INC.

5170

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT: Med Lodge

ORIGINAL

DATE <u>2-7-01</u>	SEC. <u>11</u>	TWP. <u>325</u>	RANGE <u>19W</u>	CALLED OUT <u>1:30 AM</u>	ON LOCATION <u>3:00 AM</u>	JOB START <u>9:00 AM</u>	JOB FINISH <u>9:30 AM</u>
LEASE <u>Harness</u>	WELL # <u>1-11</u>	LOCATION <u>Coldwater Kremee</u>			COUNTY <u>Comanche</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>		<u>1 1/2 W 1/4 into</u>					

CONTRACTOR <u>Duke #7</u>	OWNER <u>American Warrior</u>
TYPE OF JOB <u>surface</u>	
HOLE SIZE <u>12 1/8</u>	T.D. <u>660</u>
CASING SIZE <u>8 7/8</u>	DEPTH <u>49 654</u>
TUBING SIZE	DEPTH
DRILL PIPE	DEPTH <u>615.96</u>
TOOL <u>Baffle</u>	DEPTH <u>580.63</u>
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT <u>38.37</u>
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT <u>38 BBLs Fresh H<sub>2</sub>O</u>	

CEMENT			
AMOUNT ORDERED	<u>225</u>	<u>3x 65.35.6 + 3% CC</u>	
	<u>+ 1/4" Flo-seal</u>	<u>200</u>	<u>5x A + 3% CC</u>
	<u>+ 2% gel</u>		
COMMON	<u>100</u>	@ <u>6.35</u>	<u>635.00</u>
POZMIX		@	
GEL	<u>2</u>	@ <u>9.50</u>	<u>19.00</u>
CHLORIDE	<u>11</u>	@ <u>28.00</u>	<u>308.00</u>
	<u>AW</u>	<u>225</u>	@ <u>6.00</u> <u>1350.00</u>
	<u>FLO-SEAL</u>	<u>56</u>	@ <u>1.40</u> <u>78.40</u>
		@	
		@	
HANDLING	<u>350</u>	@ <u>1.05</u>	<u>367.50</u>
MILEAGE	<u>350</u>	<u>x 42</u>	<u>.04</u> <u>588.00</u>

EQUIPMENT	
PUMP TRUCK	CEMENTER <u>Justin Hart</u>
# <u>359-265</u>	HELPER <u>Mark Brungardt</u>
BULK TRUCK	
# <u>258-34</u>	DRIVER <u>Scott Spriggs</u>
BULK TRUCK	
#	DRIVER

RECEIVED

TOTAL 3345.91

MAY 14 2002  
5-14-02  
KCC WICHITA

SERVICE

REMARKS:  
Pipe on Bottom Break Circle 1st Circle  
Mix 225 x 65.35.6 @ 12.8# Mix  
100 x Class A 3/2 @ 15.2# Star Release  
Plug Start Disp @ 5 BPM 20 BBLs out  
lift press 35 BBLs slow rate 3 BPM  
@ 200# 38 BBLs Dump Plug 500#  
shut head in Release press  
circulated Cement ✓

DEPTH OF JOB	<u>654'</u>		
PUMP TRUCK CHARGE	<u>0-300'</u>		<u>470.00</u>
EXTRA FOOTAGE	<u>354'</u>	@ <u>.43</u>	<u>152.22</u>
MILEAGE	<u>42</u>	@ <u>3.00</u>	<u>N/C</u>
PLUG	<u>8 7/8 TRP</u>	@ <u>90.00</u>	<u>90.00</u>
		@	
		@	
			TOTAL <u>712.22</u>

CHARGE TO: American Warrior  
STREET P.O. Box 399  
CITY GARDEN CITY STATE KANSAS ZIP 67846

FLOAT EQUIPMENT

<u>8 7/8</u>			
<u>1-Baffle plate</u>	@ <u>45.00</u>		<u>45.00</u>
<u>2-Baskets</u>	@ <u>180.00</u>		<u>360.00</u>
	@		
	@		
	@		
			TOTAL <u>405.00</u>

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX		
TOTAL CHARGE	<u>4463.12</u>	
DISCOUNT	<u>446.32</u>	IF PAID IN 30 DAYS
	<u>4016.80</u>	
SIGNATURE	<u>Kenneth McGuire</u>	PRINTED NAME
	<u>KENNETH M'GUIRE</u>	

15-033-21196-0000

# ALLIED CEMENTING CO., INC. 5195

Federal Tax I.D.# 48-0727860

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

ORIGINAL

Medicine Lodge

DATE <u>2-18-01</u>	SEC. <u>11</u>	TWP. <u>32s</u>	RANGE <u>19w</u>	CALLED OUT <u>12:00 am</u>	ON LOCATION <u>2:30 am</u>	JOB START <u>5:45 am</u>	JOB FINISH <u>7:45 am</u>
LEASE <u>Harness</u>	WELL# <u>1-11</u>	LOCATION <u>Coldwater Cremyc</u>			COUNTY <u>Comanche</u>	STATE <u>KS.</u>	
OLD OR <u>NEW</u> (Circle one)				<u>Dairy Queen 1 1/2 w N/S</u>			

CONTRACTOR Duke #7

TYPE OF JOB Rotary plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 8 7/8 DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE 4 1/2 x 16.60 DEPTH 1200'

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 300 MINIMUM \_\_\_\_\_

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT Fresh H2O + mud

EQUIPMENT \_\_\_\_\_

PUMP TRUCK CEMENTER Carl B

# 352 HELPER Shane W.

BULK TRUCK

# 258 DRIVER Jason T

BULK TRUCK

# \_\_\_\_\_ DRIVER \_\_\_\_\_

OWNER American Warrior

CEMENT

AMOUNT ORDERED \_\_\_\_\_

135 sks 60:40:6

COMMON <u>A</u>	<u>81</u>	@ <u>6.35</u>	<u>514.35</u>
POZMIX	<u>54</u>	@ <u>3.25</u>	<u>175.50</u>
GEL	<u>7</u>	@ <u>9.50</u>	<u>66.50</u>
CHLORIDE		@	
		@	
		@	
		@	
		@	
HANDLING	<u>142</u>	@ <u>1.05</u>	<u>149.10</u>
MILEAGE	<u>142 x 42</u>	<u>.04</u>	<u>239.56</u>

RECEIVED

TOTAL 1144.01

MAY 14 2002  
5-14-02  
KCC WICHITA

REMARKS:

SERVICE

pump 50 sks - 1200'

50 sks - 660'

10 sks - 40'

10 sks - mouse hole

15 sks - rat hole

DEPTH OF JOB 1200'

PUMP TRUCK CHARGE \_\_\_\_\_ 470.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 42 @ 3.00 126.00

PLUG @ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL 596.00

CHARGE TO: American Warrior

STREET P.O. Box 399

CITY GARDEN CITY STATE KANSAS ZIP 67846

FLOAT EQUIPMENT

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.

You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

TOTAL CHARGE 1740.01

DISCOUNT 174.01 IF PAID IN 30 DAYS

1566.00

SIGNATURE Kenneth McGuire

KENNETH MCGUIRE  
PRINTED NAME